

CITY OF DE PERE

Engineering Division

925 S. Sixth Street, De Pere, WI | 920-339-4061 | www.deperewi.gov/engineering



March 29, 2022

ADDENDUM NO. 1 PROJECT 22-04 ALLEY RECONSTRUCTION

TO: Prospective Bidders

FROM: City of De Pere

Notice is hereby given that the contract documents for the Project 22-04 are amended as hereinafter set forth. If you will be submitting a bid for Project 22-04, you must sign this addendum and include it with your submittal.

This addendum consists of 6 pages.

CHANGES TO PROJECT BID DOCUMENTS:

1. Section 00 41 43, Bid Schedule
 - a. Delete Section 00 41 43, Bid Schedule in its entirety and insert 00 41 43R, Bid Schedule.
 - b. Bid item SD-05, Provide Asphaltic Concrete Pavement Type 3 LT 58-28 S, 2 1/4" Lower Layer has been decreased from 700 TON to 400 TON.
 - c. Bid item E-13, Delete "Luminaires Utility LED – Type 5 Pole" and Insert "Luminaires Utility LED for Type 5 Pole"
 - d. Bid item E-14, Delete "Luminaires Utility LED – Spring City" and Insert "Luminaires Utility LED for Spring City Decorative Lights"

Sincerely,

DEPARTMENT OF PUBLIC WORKS

Eric P. Rakers, P.E.
City Engineer



Acknowledged by: _____ Date: _____

SECTION 00 41 43

CITY OF DE PERE

PROJECT 22-04

BID SCHEDULE – UNIT PRICE

ITEM	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	AMOUNT BID
SANITARY SEWER					
SS-01	Remove and Relay 6" or 4" PVC Sanitary Lateral w/Slurry Backfill	LF	80	\$ _____	\$ _____
SS-02	Remove and Relay 6" or 4" PVC Sanitary Lateral	LF	460	\$ _____	\$ _____
SS-03	Dig Down and Cap Lateral	EA	1	\$ _____	\$ _____
SS-04	Connect to Existing Sanitary Lateral	EA	11	\$ _____	\$ _____
SS-05	Televise Existing Sanitary Laterals	EA	11	\$ _____	\$ _____
STORM SEWER					
ST-01	Remove and Relay 12" RCP Class V Storm Sewer	LF	25	\$ _____	\$ _____
ST-02	Provide 12" RCP Class V Storm Sewer	LF	275	\$ _____	\$ _____
ST-03	Provide 8" C900 PVC Storm Sewer Lateral w/Slurry Backfill	LF	140	\$ _____	\$ _____
ST-04	Provide 8" C900 PVC Storm Sewer Lateral	LF	100	\$ _____	\$ _____
ST-05	Provide Storm Lateral Risers w/cap at Building	EA	7	\$ _____	\$ _____
ST-06	Core Drill Storm Sewer and Provide 8" Inserta Tee	EA	6	\$ _____	\$ _____
ST-07	Provide 4' Diameter Storm Manhole	VF	6	\$ _____	\$ _____
ST-08	Remove and Replace Type B Inlet	EA	1	\$ _____	\$ _____

Project 22-04
Alley Reconstruction

City of De Pere

ITEM	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	AMOUNT BID
STORM SEWER CONTINUED					
ST-09	Provide Type B Catch Basin	EA	3	\$_____	\$_____
ST-10	Provide Type B Inlet	EA	1	\$_____	\$_____
ST-11	Provide 30" Diameter Field Inlet	EA	1	\$_____	\$_____
ST-12	Connect to Existing Structure	EA	1	\$_____	\$_____
ST-13	Televise Existing Storm Lateral	EA	1	\$_____	\$_____
ST-14	Storm Sewer Lateral Dig Down and Repair (5 feet)	EA	1	\$_____	\$_____
ST-15	Storm Sewer Dig Down and Repair Offset Joint (5 Feet)	EA	1	\$_____	\$_____
ST-16	Abandon/Remove Existing Storm Sewer Appurtenances	LS	1	\$_____	\$_____
STREET AND DRAINAGE					
SD-01	Provide Clearing and Grubbing	LS	1	\$_____	\$_____
SD-02	Unclassified Excavation	CY	2,650	\$_____	\$_____
SD-03	Provide 1 1/4" Crushed Aggregate Base Course	TON	3,060	\$_____	\$_____
SD-04	Provide Asphaltic Concrete Pavement Type 4 LT 58-28 S, 1 3/4" Upper Layer	TON	320	\$_____	\$_____
SD-05	Provide Asphaltic Concrete Pavement Type 3 LT 58-28 S, 2 1/4" Lower Layer	TON	400	\$_____	\$_____
SD-06	Provide 24" Mountable/Driveway Concrete Curb and Gutter	LF	920	\$_____	\$_____
SD-07	Provide 24" Standard/Reverse Concrete Curb and Gutter	LF	1,070	\$_____	\$_____

Project 22-04
Alley Reconstruction

City of De Pere

ITEM	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	AMOUNT BID
STREET AND DRAINAGE CONTINUED					
SD-08	Provide 14" Integral Curb Head with Sidewalk	LF	405	\$_____	\$_____
SD-09	Provide 8" Concrete Sidewalk, Ramp, and Driveway	SY	360	\$_____	\$_____
SD-10	Provide 4" Concrete Sidewalk and Behind Curb	SY	700	\$_____	\$_____
SD-11	Provide #4 Reinforcement Bars for Curb and Sidewalk	LF	720	\$_____	\$_____
SD-12	Drilled Tie Bars (Existing Sidewalk, Driveway, and Curb and Gutter)	EA	30	\$_____	\$_____
SPECIAL CONSTRUCTION					
SC-01	Provide Flexible Sign Base with 8' Pole	EA	17	\$_____	\$_____
SC-02	Inlet Protection Type A	EA	1	\$_____	\$_____
SC-03	Inlet Protection Type D	EA	6	\$_____	\$_____
SC-04	Installing Bollards	EA	8	\$_____	\$_____
SC-05	Adjust Inlet	EA	1	\$_____	\$_____
SC-06	Adjust Manhole	EA	3	\$_____	\$_____
SC-07	Construct Dumpster	LS	1	\$_____	\$_____
SC-08	Pavement Marking Epoxy 4-Inch White	LF	1,505	\$_____	\$_____
SC-09	Pavement Marking (Handicap Symbol White) Epoxy	EA	4	\$_____	\$_____
SC-10	Traffic Control	LS	1	\$_____	\$_____

Project 22-04
Alley Reconstruction

City of De Pere

ITEM	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	AMOUNT BID
ELECTRICAL					
E-01	Conduit Rigid Nonmetallic Schedule 40, 2-Inch	LF	950	\$_____	\$_____
E-02	Pull Box 24x42 Inch (Nonconductive)	EA	1	\$_____	\$_____
E-03	Concrete Base, Type 5	EA	9	\$_____	\$_____
E-04	Poles, Type 5-Aluminum Anodized Black	EA	1	\$_____	\$_____
E-05	Decorative Poles, Spring City Hancock With Ladder Rest, 9'- 2" Lamp Post	EA	8	\$_____	\$_____
E-06	Transformer Base Breakaway 11 1/2 Bolt Circle, Anodized Black with Factory Applied Black Finish	EA	1	\$_____	\$_____
E-07	Luminaire Arms Single Member Mast Arm 4-1/2 Inch Clamp, 8-foot, Anodized Black	EA	1	\$_____	\$_____
E-08	Concrete Control Cabinet Base, Type L24	EA	1	\$_____	\$_____
E-09	Lighting Control Cabinet, 120/240 24-inch	EA	1	\$_____	\$_____
E-10	Electrical Service Meter Breaker Pedestal	EA	1	\$_____	\$_____
E-11	Electrical Wire Lighting 12 AWG	LF	130	\$_____	\$_____
E-12	Electrical Wire Lighting 4 AWG	LF	3,200	\$_____	\$_____
E-13	Luminaires Utility LED for Type 5 Pole	EA	1	\$_____	\$_____
E-14	Luminaires Utility LED for Spring City Decorative Lights	EA	8	\$_____	\$_____

Project 22-04
Alley Reconstruction

City of De Pere

ITEM	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	AMOUNT BID
LANDSCAPING					
L-01	Provide Kentucky Coffee Tree - Stately Manor, 2" diameter	EA	4	\$_____	\$_____
L-02	Landscaping - Mississippi Pebble Mulch with Weed Barrier Fabric	SY	250	\$_____	\$_____
L-03	Landscaping – Topsoil, Seed, Fertilizer and Mulch	SY	65	\$_____	\$_____
L-04	Provide Backfill of Pulverized Topsoil at Trees (16" Depth)	CY	80	\$_____	\$_____
DEMOLITION					
D-01	Remove and Abandon Monitoring Well	EA	1	\$_____	\$_____
D-02	Remove and Salvage Sign	EA	3	\$_____	\$_____
TOTAL AMOUNT BID					\$_____