## CITY OF DE PERE

### **Engineering Division**

925 S. Sixth Street, De Pere, WI | 920-339-4061 | www.deperewi.gov/engineering

February 26, 2025

Dear Concrete Worker:

Applications for 2025 Concrete Worker's License can be found online at <a href="mailto:deperewi.seamlessdocs.com/f/concreteworkerslicenseapplication">deperewi.seamlessdocs.com/f/concreteworkerslicenseapplication</a>. If you have a 2024 license with the City of De Pere, it expires on **April 1, 2025**.

If you need a paper copy of the application, please contact or stop by the Engineering Department at:

Municipal Service Center 925 S Sixth Street De Pere, WI 54115 (920) 339-4061

Please be advised that if your surety bond expires before December 31, 2025, you are responsible for providing us with a new surety bond. If we do not receive your new surety bond, your sidewalk license will expire the day your surety bond expires and your name will be removed from the list of Licensed Concrete Workers located on the City's website.

A pre-pour inspection must be done by the City for all sidewalk construction once the forms are in place to verify the width and depth. To schedule an inspection please call (920) 339-4061 one business day in advance of placing concrete.

If you have any questions, please feel free to contact me at 920-339-4072 x2239.

Sincerely,

**DEPARTMENT OF PUBLIC WORKS** 

Chase Kuffel, P.E.

**Assistant City Engineer** 

Char KM.

# REVISED: OCTOBER 29, 2024 CITY OF DE PERE DEPARTMENT OF PUBLIC WORKS SIDEWALK AND DRIVEWAY APPROACH SPECIFICATIONS

The following is a list of specifications for construction of sidewalks and driveway approaches within the City of De Pere:

- 1. In accordance with Section 22-10 of the De Pere Municipal Code: "No person shall build, construct, or sawcut any concrete sidewalk upon any street in the city, construct any driveway approach between the sidewalk and curbline or sawcut any curb and/or gutter upon any street in the city without first having obtained a concrete worker's license. Property owners may construct such sidewalk or driveway approach upon any street abutting their own property without such license and without being required to furnish any bond otherwise required in this section, provided that they comply with all other provisions of this chapter.
- 2. In accordance with Section 22-15 of the De Pere Municipal Code, before a driveway or curb cut for a driveway is made, a permit shall be obtained from the Director of Public Works.
- 3. The provisions of Section 62.16 and 66.0907, Wisconsin Statutes require that no sidewalk shall be constructed or repaired unless the property owner or contractor intending to perform the work shall make written application to the Department of Public Works for establishment of the grades of said sidewalk.
- 4. Section 22-5 Subsection (c) of the De Pere Municipal Code states that after a grade line is furnished by the Department of Public Works to a contractor or property owner, it shall be the duty of the contractor or property owner to preserve said grade stakes until the concrete sidewalks have been constructed. Failure to preserve said line and grade stakes, necessitating the return of a City Official to reset stakes, will subject the contractor or property owner to the expense involved in resetting said grade stakes.
- 5. The backside of the sidewalk shall be located 6 inches from the property line towards the center of the street and shall run parallel with the property line.
- 6. The grade stakes for the installation of sidewalks will be set one foot off the backside of the sidewalk, unless otherwise specified. If there is an existing driveway, a paint mark will be placed on each side of the driveway indicating where the sidewalk will intersect the driveway.
- 7. The grade stakes for the installation of approaches shall be located on line with the backside of the sidewalk portion of the driveway. The stakes shall be located off to each side of the driveway.
- 8. A plus or minus measurement will be marked on each stake. The top of the backside of the sidewalk shall then be established by measuring either up or down from the top of the grade stake.

- 9. In accordance with the City of De Pere Department of Public Works Standard Specifications current version, which is available on the City website, and the Wisconsin Dept. of Transportation Specifications for Highway and Structure Construction, the following specifications for driveways are established:
  - Sidewalks shall be 5'-0" in width.
  - Sidewalks shall be 6" off and parallel with the right-of-way. Utilize flexible forms where required to follow radius.
  - The sidewalk shall be 4 inches in depth except through driveway approaches where they shall be 6 inches.
  - The sidewalk through the driveways and the approaches shall be placed on a 4-inch foundation of <u>compacted</u> crushed gravel or crushed stone.
  - In a cut area the foundation shall be one foot wider than the sidewalk, in a fill area the foundation shall be two feet wider than the sidewalk.
  - The sidewalks shall slope at 1.5% (3/16 inch per foot) towards the street.
  - Concrete shall be air-entrained, 6 bag mix, 28-Day Compressive Strength of 4,000 PSI.
  - Concrete shall be placed on a moist foundation.
  - Edges of sidewalks and edges adjacent to expansion joints or construction joints shall be finished with an edging tool having a radius of ¼ inch.
  - Transverse joints in the sidewalk shall be spaced at 5-foot intervals.
  - ½ inch expansion joint filler shall be placed to the full depth of the concrete on both sides of the driveway and where the approach abuts the sidewalk and the curb and gutter.
  - Transverse joints shall be placed down the center of the approach portion of the driveway. (See Detail)
  - Provide a concrete stamp per the detail.
- 10. Reinforcement is required in sidewalk per Detail C-4 under the following conditions:
  - A. Over utility trenches.
  - B. Connecting to existing sidewalk.
- 11. Whenever any obstruction such as a power pole, tree, tree roots, hydrant, inlet, valve, manhole, etc. is encountered, contact the Engineering Department before pouring the driveway or sidewalk.
- 12. It shall be the responsibility of the property owner or contractor to erect sufficient barricades to protect pedestrian and vehicular traffic at all times from excavation or construction.
- 13. Protect trees per attached Section 31 13 10 "Tree Preservation of Public Trees".
- 14. For any questions regarding driveway construction call the City of De Pere Engineering Department at 339-4061.

#### **SECTION 31 13 10**

#### TREE PRESERVATION OF PUBLIC TREES

#### PART 1 – GENERAL

#### 1.1 SUMMARY

- A. Section Includes
  - 1. Protection of above ground branches and bark.
  - 2. Protection of below ground root system and surrounding soil.

#### 1.2 REFERENCES

- A. City of De Pere Municipal Ordinance
  - 1. Chapter 30

Parks, Recreation and Tree Management

#### PART 2 – PRODUCTS

#### 2.1 MATERIALS

A. None

#### PART 3 – EXECUTION

#### 3.1 ABOVE GROUND BRANCHES AND ROOTS

- A. Tree trimming required is to be coordinated with the Engineer. The City reserves the right to trim all City trees.
- B. Hand trim damaged branches larger than two inch with handsaws, pruners, loppers, chainsaws or other specifically designed tree trimming equipment.
- C. Notify the Engineer of damage to bark. Damaged bark shall be repaired as directed by the Engineer

#### 3.2 BELOW GROUND ROOT SYSTEM AND SURROUNDING SOIL

#### A. Activities within the Protected Root Zone (PRZ)

1. The root system shall be left undisturbed in the PRZ for each tree as follows:

Tree diameter at 4.5 feet	Radius of PRZ (Measured from face of trunk	
(dbh)		
0-3 inches	3 feet	
3-8 inches	6 feet	
8-14 inches	8 feet	
14-19 inches	10 feet	
19+ inches	15 feet	

- 2. Minimize compaction.
- 3. Do not store materials and equipment.

#### B. Protection of the PRZ

- 1. Provide protection of the PRZ including but not limited to:
  - a. Fencing
  - b. Temporary raised bridges over the area for equipment.
- 2. Auger/tunnel at a minimum depth of 36 inches for utility installations.

#### C. Damaged Roots

- 1. Hand prune damaged and exposed roots larger than one inch with handsaws, pruners, loppers, chainsaws or other specifically designed root pruning equipment.
- D. Where trees are present near curb replacements, the root systems on the curb side shall be cut not more than four (4) inches beyond the edge of the new curb.
- E. For new sidewalk, limit soil disturbance to not more than four inches beyond the edge of the new sidewalk.
- F. The Engineer may route sidewalk around existing trees to minimize damage.

#### **END OF SECTION**


#### SIDEWALK REPAIR AND REPLACEMENT PROGRAM


<u>YEAR</u>	DESCRIPTION OF AREA
2025	West side of Fox River, west of RR tracks, north of Grant Street
2026	West side of Fox River, west of RR tracks, Grant to Scheuring
2027	East side of Fox River, north of Charles, west of Webster
2028	East side of Fox River, north of Charles, east of Webster
2029	West side of Fox River, east of RR tracks, north of Scheuring
2030	West side of Fox River, south of Scheuring Road
2031	East side of Fox River, south of Charles Street, west of Jordan/Ontario
2032	East side of Fox River, south of Charles, east of Jordan/Ontario


#### **GUIDELINES**


DEFECTIVE SIDEWALK AND ACCEPTABLE REPAIRS		
<u>CRITERIA</u>	<u>DEFECT</u>	REPAIRS*
Vertical Displacement	3/4" high or greater for 12" of joint	Replace Mudjack Grinding up to 2" vertical
Horizontal Displacement	Greater than 1/2" for crack 3' or longer	ReplaceLevel crack may be cleaned and filled with concrete epoxy
Profile Variance	Over 4" per slab	Replace Mudjack
Inverse Slope	Trapped water	Replace Mudjack
Surface Imperfections	50% or more of slab spalledMissing piece 3"x3" or greaterOver 10' of cracks per slab	ReplaceMissing piece up to 12" x 12" may be cleaned and filled with concrete epoxy


\*Ramping of Vertical Displacement or Concrete Overlay of sidewalk are NOT acceptable repairs.

























#### NOTE:

- 1. THE ENDS OF ALL CONCRETE WORK SHALL BE MARKED WITH A STAMP AS SHOWN, WITH THE CURRENT YEAR.
- 2. THE DATE OF CONSTRUCTION SHALL BE STAMPED ON ALL CONCRETE PAVEMENTS AND ALLEYS WITH 1-INCH NUMERALS AT THE ENDS OF EACH SECTION PAVED.

