## CITY OF DE PERE

# **PROJECT** 19-16

## MARQUETTE SQUARE DUMPSTER ENCLOSURE CONSTRUCTION

BID DATE: JUNE 27, 2019 @ 1:00 PM

Bid documents, including plans and specifications, are available for download at <a href="www.QuestCDN.com">www.QuestCDN.com</a>. The QuestCDN website can also be accessed through the City website at <a href="www.de-pere.org">www.de-pere.org</a>. On the homepage, click on the City Departments tab at the top, then click on Public Works, then Engineering, then Construction Projects, then 2019 Construction Projects. Download cost is \$15 for each contract. Bidding documents may be viewed on the QuestCDN website or at the Municipal Service Center.

Bid Tabs must be verified by staff prior to posting and will be available for viewing on the website within 7 days following the bid opening. Award information will be pending until approved by the Common Council.

## **SECTION 00 01 10**

## TABLE OF CONTENTS

## INTRODUCTORY INFORMATION

Section	<u>Title</u>
00 00 01	PROJECT MANUAL COVER
00 01 10	TABLE OF CONTENTS

## PROJECT BID DOCUMENTS

Section	<u>Title</u>
00 11 13	ADVERTISEMENT TO BID
00 21 13	INSTRUCTIONS TO BIDDERS
00 41 13	BID FORM
00 41 43	BID SCHEDULE
00 43 13	BID BOND
00 43 33	PROPOSED PRODUCTS FORM
00 43 36	TABULATION OF SUBCONTRACTOR

## CONTRACTING REQUIREMENTS

Section	<u>Title</u>
00 51 00	NOTICE OF AWARD
00 52 13	CONTRACT
00 55 00	NOTICE TO PROCEED
00 61 13	PAYMENT BOND
00 61 16	PERFORMANCE BOND
00 62 76	APPLICATION FOR PAYMENT
00 65 16	CERTIFICATE OF SUBSTANTIAL COMPLETION

## **Marquette Square Dumpster Enclosure Construction**

## DIVISION 1 GENERAL REQUIREMENTS

Section	<u>Title</u>
01 10 00	SUMMARY OF WORK
01 22 02	MEASUREMENT AND PAYMENT STORM SEWER
01 22 04	MEASUREMENT AND PAYMENT STREET AND DRAINAGE
	CONSTRUCTION
01 22 05	MEASUREMENT AND PAYMENT SPECIAL CONSTRUCTION
01 29 00	PAYMENT PROCEDURES
01 32 33	CONSTRUCTION PHOTOGRAPHS
01 33 00	SUBMITTALS
01 41 00	REGULATORY REQUIREMENTS
01 71 23	FIELD ENGINEERING

## SUPPLEMENTAL SPECIAL PROVISIONS

Section	<u>Title</u>
04 22 00	CONCRETE UNIT MASONRY
08 15 00.01	VINYL FENCING DOORS

## **CITY OF DE PERE 2019 STANDARD SPECIFICATIONS**

## CONTRACTING REQUIREMENTS

Section	<u>Title</u>
00 70 00	GENERAL CONDITIONS
	(See City of De Pere 2019 Standard Specifications)
DIVISION 31 –	<b>EARTHWORK</b> (See City of De Pere 2019 Standard Specifications)
DIVISION 32 –	<b>EXTERIOR IMPROVEMENTS</b> (See City of De Pere 2019 Standard Specifications)
DIVISION 33 –	UTILITIES (See City of De Pere 2019 Standard Specifications)

#### **SECTION 00 11 13**

## **JUNE 6, 2019 – JUNE 13, 2019**

#### CITY OF DE PERE

#### ADVERTISEMENT TO BID

#### **PROJECT 19-16**

#### MARQUETTE SQUARE DUMPSTER ENCLOSURE CONSTRUCTION

Sealed proposals will be received by the Board of Public Works of the City of De Pere at the Municipal Service Center, 925 South Sixth Street, De Pere, Wisconsin 54115, until 1:00 PM on Thursday, June 27, 2019, at which time they will be publicly opened and read aloud.

Project 19-16 for which proposals are being sought includes the following approximate quantities:

- One (1) dumpster enclosures with the following quantities:
  - An 18-foot by 26-foot by eight-inch concrete slab with an integral 12-inch by 12-inch footing and two #4 bars continuous at the perimeter for the enclosure wall to sit atop. Concrete slab is to have an eight-inch to 12-inch crushed aggregate base.
  - o 52 feet of enclosure wall constructed of an eight-inch split faced concrete masonry unit wall. Masonry unit wall shall be constructed with four-foot #4 bars at 24-inches on center extending a half-foot into the concrete slab.
  - o Two (2) enclosure gates.
  - o Three (3) six-inch diameter concrete filled galvanized steel pipes (field painted) set in 18-inch diameter concrete footing extending four feet below grade.
  - o One (1) four-foot wide, hinge mounted access door.
- 15-inch crushed aggregate base restoration. Asphalt restoration and pavement markings to be completed by others.
- Asphalt pavement saw cutting and removals.

Complete digital project bidding documents are available for viewing and or downloading at <a href="https://www.QuestCDN.com">www.QuestCDN.com</a> or may be examined at the office of the Director of Public Works. Digital plan documents may be downloaded for \$15 by inputting Quest project #6389855 on Quest's Project Search page. The QuestCDN website can also be accessed through the City website at <a href="https://www.de-pere.org">www.de-pere.org</a>. On the homepage, click on the City Departments tab at the top, then click on Public Works, then Engineering, then Construction Projects, then 2019 Construction Projects.

Each proposal shall be accompanied by a certified check or bid bond in an amount equal to five percent (5%) of the bid, payable to the City of De Pere, as a guarantee that if the bid is accepted, the bidder will execute a contract and furnish a contract bond as set forth in the General Conditions of the City of De Pere. In case the bidder fails to file such contract and bond, the amount of the check or bid bond shall be forfeited to the City of De Pere as liquidated damages.

6/6/2019 00 11 13-1 Advertisement to Bid

## **Marquette Square Dumpster Enclosure Construction**

The letting of the contract is subject to the provisions of the following Wisconsin Statutes:

Section 62.15 regarding Public Works.

Section 66.0901(3) regarding Prequalification of Contractor.

Each bidder shall pre-qualify by submitting proof of responsibility on forms furnished by the Director of Public Works. Such forms shall be filed with the Director of Public Works no later than 4:00 P.M., Monday, June 24, 2019. Prospective bidders who have previously submitted such forms subsequent to January 1, 2019 will not be required to separately submit such form for this project.

The City of De Pere reserves the right to reject any or all bids, to waive any informalities in bidding and to accept any proposal which the Common Council deems most favorable to the interest of the City of De Pere.

Dated this 6<sup>th</sup> day of June, 2019.

Board of Public Works City of De Pere Eric Rakers, P.E. City Engineer

Project 19-16

#### **SECTION 00 21 13**

#### INSTRUCTIONS TO BIDDERS

#### ARTICLE 1 – DEFINED TERMS

1.1 Terms used in these Instructions to Bidders have the meanings indicated in the General Conditions. Additional terms used in these Instructions to Bidders have the meanings indicated below:

None

## ARTICLE 2 – COPIES OF BIDDING DOCUMENTS

- 2.1 Complete sets of the Bidding documents in the number and for the deposit sum, if any, stated in the Advertisement or Invitation to Bid may be obtained as stated in the Advertisement for bids.
- 2.2 Complete sets of Bidding Documents shall be used in preparing Bids; Owner does not assume any responsibility for errors or misinterpretations resulting from the use of incomplete sets of Bidding Documents.
- 2.3 Owner, in providing the Bidding Documents on the terms stated in the Advertisement for Bids, does so only for the purpose of obtaining Bids for the Work and does not confer a license or grant for any other use.

## ARTICLE 3 – QUALIFICATIONS OF BIDDERS

3.1 In accordance with Section 66.0901(3), each bidder shall pre-qualify by submitting proof of responsibility on forms furnished by the Director of Public Works. Such forms shall be filed with the Director of Public Works as stated in the advertisement for Bids. Prospective bidders who have previously submitted such forms after January 1<sup>st</sup> of this year will not be required to separately submit such form for this project.

## ARTICLE 4 – EXAMINATION OF BIDDING DOCUMENTS, OTHER RELATED DATA AND

SITE

- 4.1 Provisions concerning responsibilities for the adequacy of data furnished to prospective Bidders with Underground Facilities, and possible changes in the Bidding Documents due to differing or unanticipated conditions appear in the General Conditions.
- 4.2 Underground Facilities
  - A. Information and data shown or indicated in the Bidding Documents with respect to existing Underground Facilities at or contiguous to the Site is based upon information and data furnished to Owner and Engineer by owners of such Underground Facilities,

6/6/2019 00 21 13-1 Instructions to Bidders

including Owner, or others.

## 4.3 Subsurface and Physical Conditions

#### A. The technical data includes:

- 1. Those reports known to Owner of explorations and tests of subsurface conditions at or contiguous to the Site; and
- 2. Those drawings known to Owner of physical conditions relating to existing surface or subsurface structures at the Site (except underground Facilities).
- 3. No reports of explorations or tests of subsurface conditions at or contiguous to the Site, or drawings of physical conditions relating to existing surface or subsurface structures at the Site, are known to Owner.
- B. Limited Reliance by Contractor on Technical Data Authorized: Contractor may rely upon the accuracy of the "technical data" contained in such reports and drawings, but such reports and drawings are not Contract Documents. Contractor may not rely upon or make any claim against Owner, or any of their officers, directors, members, partners, employees, agents, consultants, or subcontractors with respect to:
  - 1. the completeness of such reports and drawings for Contractor's purposes, including but not limited to, any aspects of the means, methods, techniques, sequences, and procedures of construction to be employed by Contractor, and safety precautions and programs incident thereto; or
  - 2. Other data, interpretations, opinions, and information contained in such reports or shown or indicated in such drawings; or
  - 3. Any Contractor interpretation of or conclusion drawn from any "technical data" or any such other data, interpretations, opinions, or information.
- 4.4 On request, Owner will provide Bidder access to the Site to conduct such examinations, investigations, explorations, tests, and studies as Bidder deems necessary for submission of a Bid. Bidder shall fill all holes and clean up and restore the Site to its former condition upon completion of such explorations, investigations, tests, and studies. Bidder shall comply with all applicable Laws and Regulations relative to excavation and utility locates.
- 4.5 Reference is made to Section 01 10 00: Summary of Work, for work that will be completed and for the identification of the general nature of other work that is to be performed at the Site by Owner or others (such as utilities and other prime contractors) that relates to the Work contemplated by these Bidding Documents. On request, Owner will provide to each Bidder for examination access to or copies of Contract Documents (other portions thereof related to price) for such other work.
- 4.6 It is the responsibility of each Bidder before submitting a Bid to:
  - A. Examine and carefully study the Bidding Documents, the other related data identified in the Bidding Documents, and any Addenda;

6/6/2019 00 21 13-2 Instructions to Bidders

- B. Visit the Site and become familiar with and satisfy Bidder as to the general, local, and Site conditions that may affect cost, progress, and performance of the Work;
- C. Become familiar with and satisfy Bidder as to all federal, state, and local Laws and Regulations that may affect cost, progress, and performance of the Work;
- D. Obtain and carefully study (or accept consequences of not doing so) all examinations, investigations, explorations, tests, studies, and data concerning conditions (surface, subsurface, and Underground Facilities) at or contiguous to the Site which may affect cost, progress, or performance of the Work or which relate to any aspect of the means, methods, techniques, sequences, and procedures of construction to be employed by Bidder, including applying any specific means, methods, techniques, sequences, and procedures of construction expressly required by the Bidding Documents, and safety precautions and programs incident thereto;
- E. Agree at the time of submitting its Bid that no further examinations, investigations, explorations, tests, studies, or data are necessary for the determination of its Bid for performance of the Work at the price(s) bid and within the times and in accordance with the other terms and conditions of the Bidding Documents;
- F. Become aware of the general nature of the work to be performed by Owner and others at the Site that relates to the Work as indicated in the Bidding Documents;
- G. Correlate the information known to Bidder, information and observations obtained from visits to the Site, reports and drawing identified in the Bidding Documents, and all additional examinations, investigations, explorations, tests, studies, and data with the Bidding Documents;
- H. Promptly give Engineer written notice of all conflicts, errors, ambiguities, or discrepancies, that bidder discovers in the Bidding Documents and confirm that the written resolution thereof by Engineer is acceptable to Bidder; and
- I. Determine that the Bidding Documents are generally sufficient to indicate and convey understanding of all terms and conditions for the performance of the Work.
- 4.7 The submission of a Bid will constitute an incontrovertible representation by Bidder that Bidder has complied with every requirement of this Article 4, that without exception the Bid is premised upon performing and furnishing the Work required by the Bidding Documents and applying any specific means, methods, techniques, sequences, and, procedures of construction that may be shown or indicated or expressly required by the Bidding Documents, that Bidder has given Engineer written notice of all conflicts, errors, ambiguities, and discrepancies that Bidder has discovered in the Bidding Documents and the written resolutions thereof by Engineer are acceptable to Bidder, and that the Bidding Documents are generally sufficient to indicate and convey understanding of all terms and conditions for performing and furnishing the Work.

6/6/2019 00 21 13-3 Instructions to Bidders

#### ARTICLE 5 – SITE AND OTHER AREAS

5.1 The Site is identified in the Bidding Documents. Easements for permanent structures or permanent changes in existing facilities are to be obtained and paid for by Owner unless otherwise provided in the Bidding Documents. All additional lands and access thereto required for temporary construction facilities, construction equipment, or storage of materials and equipment to be incorporated in the Work are to be obtained and paid for by Contractor.

#### ARTICLE 6 - INTERPRETATIONS AND ADDENDA

- 6.1 All questions about the meaning or intent of the Bidding Documents are to be submitted to Engineer in writing. Interpretations or clarifications considered necessary by Engineer in response to such questions will be issued by Addenda mailed or delivered to all parties recorded by Engineer as having received the Bidding Documents. Questions received less than ten days prior to the date for opening of Bids may not be answered. Only questions answered by Addenda will be binding. Oral and other interpretations or clarifications will be without legal effect.
- Addenda may be issued to clarify, correct, or change the Bidding Documents as deemed advisable by Owner and Engineer.

#### ARTICLE 7 – BID SECURITY

- 7.1 A Bid shall be accompanied by Bid security made payable to Owner in an amount of 5 percent of Bidder's maximum Bid price and in the form of a certified check or bank money order or Bid bond (on the form attached) issued by a surety meeting the requirements of the General Conditions. Submittal of a Bid Bond on a form other than the Bid Bond form included in the Bidding Documents may be cause for rejection of Bid.
- 7.2 The Bid security of the Successful Bidder will be retained until such Bidder has executed the Contract documents, furnished the required contract security and met the other conditions of the Notice of Award, whereupon the Bid security will be returned. If the Successful Bidder fails to execute and deliver the Contract Documents and furnish the required contract security within 15 days after the Notice of Award, Owner may annul the Notice of Award and the Bid security of that Bidder will be forfeited. The Bid security of other Bidders whom Owner believes to have a reasonable chance of receiving the award may be retained by Owner per the General Conditions.
- 7.3 Bid security of other Bidders whom Owner believes do not have a reasonable chance of receiving the award will be returned within seven days after the Bid opening.

#### ARTICLE 8 – CONTRACT TIMES

8.1 The number of days within which, or the dates by which, Milestones are to be achieved and the Work is to be substantially completed and ready for final payment are set forth in

6/6/2019 00 21 13-4 Instructions to Bidders

the Bid Form and Summary of Work.

## ARTICLE 9 – LIQUIDATED DAMAGES

9.1 Provisions for liquidated damages are set forth in the General Conditions.

## ARTICLE 10 – SUBSTITUTE AND "OR-EQUAL" ITEMS

10.1 The Contract, if awarded, will be on the basis of materials and equipment specified or described in the Bidding Documents without consideration of possible substitute or "orequal" items. Whenever it is specified or described in the Bidding Documents that a substitute or "or-equal" item of material or equipment may be furnished or used by Contractor if acceptable to Engineer, application for such acceptance will not be considered by Engineer until after the Effective Date of the Bid Form and Summary of Work.

## ARTICLE 11 – SUBCONTRACTORS, SUPPLIERS, AND OTHERS

- 11.1 The Bidder shall submit with the Bid to Owner a list of all such Subcontractors, Suppliers, individuals, or entities proposed for those portions of the Work for which such identification is required. Such list shall be accompanied by an experience statement with pertinent information regarding similar projects and other evidence of qualification for each such Subcontractor, Supplier, individual, or entity, Owner may, before the Notice of Award is given, request apparent Successful Bidder to submit a substitute, in which case apparent Successful Bidder shall submit an acceptable substitute, Bidder's Bid price will be increased (or decreased) by the difference in cost occasioned by such substitution, and Owner may consider such price adjustment in evaluating Bids and making the Contract award.
- 11.2 If apparent Successful Bidder declines to make any such substitution, Owner may award the Contract to the next lowest Bidder that proposed to use acceptable Subcontractors, Suppliers, individuals, or entities. Declining to make requested substitutions will not constitute grounds for forfeiture of the Bid security of any Bidder. Any Subcontractor, Supplier, individual, or entity so listed and against which Owner makes no written objection prior to the giving of the Notice of Award will be deemed acceptable to Owner subject to revocation of such acceptance after the Effective Date of the Agreement.
- 11.3 Contractor shall not be required to employ any Subcontractor, Supplier, individual, or entity against whom Contractor has reasonable objection.

## ARTICLE 12 - PREPARATION OF BID

- 12.1 The Bid form is included with the Bidding documents.
- All blanks on the Bid Form shall be completed by printing in ink or by typewrite and the Bid signed in ink. Erasures or alterations shall be initialed in ink by the person signing

6/6/2019 00 21 13-5 Instructions to Bidders

- the Bid Form. A Bid price shall be indicated for each alternative, and unit price item listed therein, or the words "No Bid," "No Change," or "Not Applicable" entered.
- 12.3 A Bid by a corporation shall be executed in the corporate name by the president or a vice-president or other corporate office accompanied by evidence of authority to sign. The corporate seal shall be affixed and attested by the secretary or an assistant secretary. The corporate address and state of incorporations shall be shown below the seal.
- 12.4 A Bid by a partnership shall be executed in the partnership name and signed by a partner (whose title must appear under the signature), accompanied by evidence of authority to sign. The official address of the partnership shall be shown below the signature.
- 12.5 A Bid by a limited liability company shall be executed in the name of the firm by a member and accompanied by evidence of authority to sign. The state of formation of the firm and the official address of the firm shall be shown below the signature.
- 12.6 A Bid by an individual shall show the Bidder's name and official address.
- 12.7 A Bid by a joint venture shall be executed by each joint venture in the manner indicated on the Bid Form. The official address of the joint venture shall be shown below the signature.
- 12.8 All names shall be typed or printed in ink below the signatures.
- 12.9 The Bid shall contain an acknowledgement of receipt of all Addenda, the numbers of which shall be filled in on the Bid Form.
- 12.10 The address and telephone number for communications regarding the Bid shall be shown.
- 12.11 The Bid shall contain evidence of Bidder's authority and qualification to do business in the state where the Project is located or covenant to obtain such qualification prior to award of the Contract. Bidder's state contractor license number, if any, shall also be shown on the Bid Form.

## ARTICLE 13 – BASIS OF BID; COMPARISON OF BIDS

#### 13.1 Unit Price

- A. Bidders shall submit a Bid on a unit price basis for each item of Work listed in the Bid Schedule.
- B. The total of all estimated prices will be the sum of the products of the estimated quantity of each item and the corresponding unit price. The final quantities and Contract Price will be determined in accord with the General Conditions.
- C. Discrepancies between the multiplication of units of Work and unit prices will be

6/6/2019 00 21 13-6 Instructions to Bidders

resolved in favor of the unit prices. Discrepancies between the indicated sum of any column of figures and the correct sum thereof will be resolved in favor of the correct sum. Discrepancies between words and figures will be resolved in favor of the words.

#### ARTICLE 14 – SUBMITTAL OF BID

- 14.1 A Bid shall be submitted no later than date and time prescribed and at place indicated in Advertisement for Bids and shall be enclosed in a plainly marked package with the Project title (and, if applicable, designated portion of the Project for which the Bid is submitted), name and address of Bidder, and shall be accompanied by the Bid security and other required documents. If a Bid is sent by mail or other delivery system, sealed envelope containing the Bid shall be enclosed in a separate package plainly marked on outside with the notation "BID ENCLOSED." A mailed Bid shall be addressed to City of De Pere, Municipal Service Center, 925 S. Sixth Street, De Pere, WI 54115. Electronically transmitted Bids will not be accepted.
- 14.2 See Bid Form for a list of documents typically required to be submitted with the Bid.

#### ARTICLE 15 – MODIFICATION AND WITHDRAWAL OF BID

- 15.1 A Bid may be modified or withdrawn by an appropriate document duly executed in the manner that a Bid must be executed and delivered to the place where Bids are to be submitted prior to the date and time for the opening of Bids.
- 15.2 If within 24 hours after Bids are opened, any Bidder files a duly signed written notice with Owner and promptly thereafter demonstrates to the reasonable satisfaction of Owner that there was a material and substantial mistake in the preparation of its Bid, that Bidder may withdraw its Bid, and the Bid security will be returned. Thereafter, if the Work is rebid, that Bidder will be disqualified from further bidding on the Work.

## ARTICLE 16 – OPENING BIDS

Bids will be opened at the time and place indicated in the Advertisement or Invitation to Bid and, unless obviously non-responsive, read aloud publicly. An abstract of the amounts of the base bids and major alternates, if any, will be made available to Bidders after the opening of Bids.

#### ARTICLE 17 – BIDS REMAIN SUBJECT TO ACCEPTANCE

17.1 All bids will remain subject to acceptance for the period of time stated in the General Conditions, but Owner may, in its sole discretion, release any Bid and return the Bid security prior to the end of this period.

6/6/2019 00 21 13-7 Instructions to Bidders

#### ARTICLE 18 – EVALUATION OF BIDS AND AWARD OF CONTRACT

- 18.1 Owner reserves the right to reject any or all Bids, including without limitation, nonconforming, nonresponsive, unbalanced, or conditional Bids. Owner further reserves the right to reject the Bid of any Bidder whom it finds, after reasonable inquiry and evaluation, to not be responsible. Owner may also reject the Bid of any Bidder if Owner believes that it would not be in the best interest of the Project to make an award to that Bidder. Owner also reserves the right to waive all informalities not involving price, time, or changes in the Work and to negotiate contract terms with the Successful Bidder.
- 18.2 More than one Bid for the same Work from an individual or entity under the same or different names will not be considered. Reasonable grounds for believing that any Bidder has an interest in more than one Bid for the Work may be cause for disqualification of that Bidder and the rejection of all Bids in which that Bidder has an interest.
- 18.3 In evaluating Bids, Owner will consider whether or not the Bids comply with the prescribed requirements, and such alternates, unit prices and other data, as may be requested in the Bid Form or prior to the Notice of Award.
- In evaluating Bidders, Owner will consider the qualifications of Bidders and may consider the qualifications and experience of Subcontractors, Supplier, and other individuals or entities proposed for those portions of the Work for which the identify of Subcontractors, Suppliers, and other individuals or entities must be submitted as provided in the Supplementary Conditions.
- 18.5 Owner may conduct such investigations as Owner deems necessary to establish the responsibility, qualifications, and financial ability of Bidders, proposed Subcontractors, Suppliers, individuals, or entities to perform the Work in accordance with the Contract Documents.
- 18.6 Bidder agrees to waive any claim it has or may have against the Owner and the respective employees arising out of or in connection with the administration, evaluation or recommendation of any Bid.
- 18.7 If the Contract is to be awarded, Owner will award the Contract to the lowest responsible responsive Bidder whose Bid is in the best interests of the Project.

## ARTICLE 19 - CONTRACT SECURITY AND INSURANCE

19.1 The General Conditions set forth Owner's requirements as to performance and payment bonds and insurance. When the Successful Bidder delivers the executed Agreement to Owner, it shall be accompanied by such bonds and a certificate of insurance.

6/6/2019 00 21 13-8 Instructions to Bidders

#### Mai quette square Dumpster Enclosure Const

ARTICLE 20 – SIGNING OF AGREEMENT

20.1 When Owner gives a Notice of Award to the Successful Bidder, it shall be accompanied by the required number of unsigned counterparts of the Agreement with the other Contract Documents which are identified in the Agreement as attached thereto. Within 10 days thereafter, Successful Bidder shall sign and deliver the required number of counterparts of the Agreement and attached documents to Owner. Within ten days thereafter, Owner shall deliver one fully signed counterpart to Successful Bidder with a complete set of Drawings with appropriate identification.

END OF SECTION

6/6/2019 00 21 13-9 Instructions to Bidders

Addendum No.

#### **SECTION 00 41 13**

#### CITY OF DE PERE

#### **BID FORM**

#### **PROJECT 19-16**

This bid, submitted by the undersigned Bidder to the City of De Pere, in accordance with the Advertisement or Invitation to Bid, which will be received until 1:00 PM. Thursday, June 27, 2019 is to furnish and deliver all materials, and to perform and do all work on the project designated by November 1, 2019.

Bidder has examined and carefully prepared the bid from the plans and specifications and has checked the same in detail before submitting said proposal or bid; and that said bidder or bidder's agents, officer or employees have not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with this proposal or bid.

Bidder has examined and carefully studied the Bidding Documents, other related data identified in the Bidding Documents, and the following Addenda, receipt of which is hereby acknowledged:

Addendum Date

TOTAL BID PRICE: \$

RASI	S OF BID:	
DASI	SOLDE.	
	Bidder will complete the Work in accordance with the Contract documents for the following prices (s):	ıe
	As stated in the attached Unit Price Bid Schedule.	
	Unit Prices have been computed in accordance with the General Conditions.	
	Bidder acknowledges that estimated quantities are not guaranteed, and are solely for the purpose of comparison of Bids, and final payment for all Unit Price Bid items will based on actual quantities, determined as provided in the Contract Documents.	

6/6/2019 00 41 13-1 Bid Form

## **Marquette Square Dumpster Enclosure Construction**

ATTACHMENTS TO	O THIS	BID
----------------	--------	-----

The following documents are submitted with and made a condition of this	Bid:
---	------

- A. Required Bid Security
- B. Unit Price Bid Schedule (Section 00 41 43)
- C. Proposed Products Form (Section 00 43 33)
- B. Tabulation of Subcontractors (Section 00 43 36)

BID SUBMITTAL
This Bid is submitted by of,
The Bidder, being duly sworn, does dispose that they are an authorized representative of
Bidder, if Bidder is:
An Individual
Name (typed or printed):
By:(Individual's signature)
(Individual's signature)
Doing business as:
A Partnership  Partnership Name:
By:(Signature of general partner – attach evidence of authority to sign)
(Signature of general partner – attach evidence of authority to sign)
Name (typed or printed):
A Corporation
<u> 11 corporation</u>
Corporation Name:
State of Incorporation:
Type (General Business, Professional, Service, Limited Liability):
By:

(Signature – attach evidence of authority to sign)

## **Marquette Square Dumpster Enclosure Construction**

Name (typed or printed):	
Title:	
(CORPORATE SEA	L)
Attest	
Date of Qualification to do business in Wisconsin is/_	
Joint Venture	
Name of Joint Venture:	
First Joint Venturer Name:	(SEAL)
By:(Signature of first joint venture partner – at	tach evidence of authority to sign)
Name (typed or printed):	
Title:	
Second Joint Venturer Name:	(SEAL)
By:	
By:(Signature of second joint venture partner -	- attach evidence of authority to sign)
Name (typed or printed):	
Title:	
(Each joint venture must sign. Manner of signing corporation that is a party to joint venture should be in ma	
Bidder's Business Address	
Phone No	Fax No.
E-mail	
SUBMITTED on, 20	
State Contractor License No.	(if applicable).

## **SECTION 00 41 43**

## **CITY OF DE PERE**

## **PROJECT 19-16**

## **BID SCHEDULE – UNIT PRICE**

ITEM	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	AMOUNT BID
STORM	1 SEWER				
ST-01	Provide Type B Inlet	EA	1	\$	\$
STREET AND DRAINAGE					
SD-01	Remove Curb and Gutter	LF	35	\$	\$
SD-02	Provide 24" Concrete Curb and Gutter	LF	40	\$	\$
SD-03	Drilled Tie Bars (Existing Curb and Gutter)	EA	2	\$	\$
SD-04	Landscaping: Topsoil, Seed, Fertilizer and Mulch No. 40 Seed Mix	SY	30	\$	\$
SPECIAL CONSTRUCTION					
SP-01	Dumpster Enclosure Construction & Restoration	LS	1	\$	\$
SP-02	Remove Tree and Grind Stump	ID	20	\$	\$
TOTAL AMOUNT BID:				\$	

## **SECTION 00 43 13**

## **CITY OF DE PERE**

## **BID BOND**

KNOW ALL	MEN BY THE	ESE PRESENTS	: That		,
as Principal, h	nereinafter call	ed Principal, and			
•		• •	eld and firmly bound un consin, as Obligee, here	•	
			do	llars (\$	)
for the payr administrators	ment whereof s, successors an	Principal and assigns, jointl	Surety bind themselve y and severally, firmly by	es, their heirs, e y these presence.	xecutors,
equipment an drawings and	d incidentals r l specification	necessary to comes prepared by to	to the City for furnishin aplete the work of Project the Director of Public V and is hereinafter referred	et 19-16 in accorda Works of said Cit	ance with
shall be awa accordance w	rded the cont	ract for said pr en this obligatio	OF THIS OBLIGATION oject and Principal shann shall be null and void;	ll enter into a co	ntract in
1. The liability of Surety shall in no event exceed the penalty of this bond.					
2. Any suits at law or proceedings, in equity brought or to be brought against Sure to recover any claim hereunder shall be executed within six (6) months from the date of this instrument.					
Signed and se	aled this	day of	, 20	<u>_</u> .	
In the presence	ee of:				
WITNI	200		DD INICID A I	(CEAL)	
WITNE	200		PRINCIPAL	(SEAL)	
WITNE	ESS		SURETY	(SEAL)	

## **SECTION 00 43 33**

## PROPOSED PRODUCTS FORM

The following is a list of material, type or model numbers and manufacturers used in the preparation of this proposal and to be used on this project:

ITEM	MATERIAL	SUPPLIER
Storm Sewer (PVC/RCP)		
Inlets		
Split Face Concrete		
Masonry Unit		
Chesterfield Fence		

6/6/2019 00 43 33-1 Proposed Products Form

#### **SECTION 00 43 36**

## **TABULATION OF SUBCONTRACTORS**

The following information is submitted which gives the name, business address, and portion of work for each subcontractor that will be used in the work if the bidder is awarded the contract, and no subcontractor doing work in excess of one-half of one percent of the total amount of the bid and who is not listed will be used without the written approval of the Engineer. Additional numbered pages outlining this portion of the proposal may be attached to this page.

<u>PORTION OF WORK</u> <u>BUSINESS NAME</u> <u>BUSINESS ADDRESS</u>

6/6/2019 00 43 36-1 Tabulation of Subcontractors

## Project 19-16 Marquette Square Dumpster Enclosure Construction

## **SECTION 00 51 00**

## NOTICE OF AWARD

NOTICE OF TWIND
(Contractor) (Contractor Name) (Address) (Address)
Project Description: 19-16 Marquette Square Dumpster Enclosure Construction
The City has considered the proposal submitted by you dated (BID DATE) for the above-described project in response to its Advertisement for Bids dated June 6, 2019 and June 13, 2019.
You are hereby notified that the Common Council of the City of De Pere has accepted your bid of (Contract Amount \$00).
You are required to execute the Contract and furnish the required Performance Bond, Payment Bond and Certificates of Insurance within ten (10) calendar days from the date of this notice to you.
If you fail to execute said Agreement and to furnish said bonds within ten (10) days from the date of this notice, said City will be entitled to consider all your rights arising out of the City's acceptance of your bid as abandoned and as a forfeiture of your Bid Bond. The City will be entitled to such other rights as may be granted by law.
You are required to return an acknowledged copy of this NOTICE OF AWARD to the City.
Dated thisth day of2019.
DEPARTMENT OF PUBLIC WORKS
BY: Eric P. Rakers, P.E. City Engineer
ACCEPTANCE OF NOTICE
Receipt of the above NOTICE OF AWARD is hereby acknowledged by:
, this the day of, 20
By:

6/6/2019 00 51 00-1 Notice of Award

## **Marquette Square Dumpster Enclosure Construction**

#### **SECTION 00 52 13**

#### **CONTRACT**

This Contract, made and entered into this day \_\_\_\_\_\_ (date to be affixed by City), by and between (Contractor Name), hereinafter called Contractor, and the City of De Pere, a municipal corporation of the State of Wisconsin, hereinafter called City.

WITNESSETH: That, in consideration of the covenants and agreements herein contained, to be performed by the parties hereto, and of the payments hereinafter agreed to be made, it is mutually agreed as follows:

## ARTICLE I - SCOPE OF WORK

The Contractor shall furnish all materials and all equipment and labor necessary, and perform all work shown on the drawings and described in the specifications for the project entitled Project 19-16 Marquette Square Dumpster Enclosure Construction, all in accordance with the requirements and provisions of the following documents, which are hereby made a part of this Contract:

- (a) Advertisement for Bids, dated (1<sup>st</sup> Advertising Date) and (2<sup>nd</sup> Advertising Date).
- (b) Drawings designated for Project Number and Name dated (1<sup>st</sup> Advertising Date).
- (c) City of De Pere 2019 Construction Specifications.
- (d) Special Provisions dated (1<sup>st</sup> Advertising Date)
- (e) Proposal submitted by (Contractor Name) dated Bid Date.
- (f) Addenda No. dated

#### ARTICLE II - TIME OF COMPLETION

- (a) The work to be performed under the Contract shall be commenced within (number spelled out) (\_\_) calendar days after receipt of written notice to proceed. The work shall be completed within (Number spelled out) (\_\_) calendar days ) or (specific calendar dates) after receipt of Notice to Proceed.
- (b) Time is of the essence with respect to the date of completion herein above stated. Failure to complete the work within the number of calendar days stated in this Article, or interim dates included in the work sequence in Section 01 10 00, Summary of Work, including any extensions granted thereto, shall entitle the City to deduct from the monies due the Contractor an amount equal to Update based on 00 70 00 General Conditions (Page 22)(\$) per day for each calendar day of delay in the completion of the work. Such amount shall be considered and treated not as a penalty but as liquidated damages, which the City will

6/6/2019 00 52 13-1 Contract

## **Marquette Square Dumpster Enclosure Construction**

sustain, by failure of the Contractor to complete the work within the time stated.

## ARTICLE III - PAYMENT

- (a) The Contract Sum. The City shall pay to the Contractor for the performance of the Contract the amounts determined for the total number of each of the following units of work completed at the unit price stated thereafter. The number of units contained in this schedule is approximate only, and the final payment shall be made for the actual number of units that are incorporated in or made necessary by the work covered by the Contract.
- (b) Progress Payments. The City shall make payments on account of the Contract as follows:
  - 1. On not later than the fourth Friday day of every month the Contractor shall present to the City an invoice covering an estimate of the amount and proportionate value of the work done as verified by the City under each item of work that has been completed from the start of the job up to and including the fourth Friday of the preceding month, and the value of the work so completed determined in accordance with the schedule of unit prices for such items, together with such supporting evidence as may be required. This invoice shall also include an allowance for the cost of such materials and equipment required in the permanent work as have been delivered to the site but not as yet incorporated in the work.
  - 2. On not later than the third week of the following month, the City shall, after deducting previous payments made, pay to the Contractor 95% of the amount of the approved invoice, retaining 5% of the estimate of work done until 50% of the work has been completed. At 50% completion of the work, the previous retainage shall not yet be paid, but further partial payments shall be made in full to the contractor without additional retainage being taken unless the engineer certifies that the work is not proceeding satisfactorily. If the work is not proceeding satisfactorily, additional amounts may be retained. After substantial completion, an amount retained may be paid to the contractor, keeping retained only such amount as is needed for the remaining work.
  - 3. The Contractor shall notify the City in writing when all work under this Contract has been completed. Upon receipt of such notice the City shall, within a reasonable time, make the final inspection and issue a final certificate stating that the work provided for in this Contract has been completed and is accepted under the terms and conditions thereof, and that the entire balance due the Contractor as noted in said final certificate is due and payable. Before issuance of the final certificate the Contractor shall submit evidence satisfactory to the City that payrolls, material bills, and other indebtedness connected with the work under this Contract have been paid. The City shall make final payment as soon after issuance of the final certificate as practicable.

6/6/2019 00 52 13-2 Contract

## **Marquette Square Dumpster Enclosure Construction**

#### ARTICLE IV - CONTRACT DOCUMENTS

## (a) Contents

- 1. The Contract documents consist of the following:
  - a. This Contract (pages 00 52 13-1 to 0052-13-2, inclusive).
  - b. Payment bond (pages 00 61 13-1 to 00 61 13-2, inclusive).
  - c. Performance bond (page 00 61 16-1).
  - d. General Conditions (pages 00 70 00-1 to 00 70 00-27, inclusive).
  - e. Specifications as listed in the table of contents of the Project Manual.
  - f. Drawings consisting of \_\_\_ sheets with each sheet bearing the following general title: \_\_\_[or] the Drawings listed on attached sheet index.
  - g. Addenda (numbers \_\_\_\_ to \_\_\_ inclusive), dated\_\_\_\_.
  - h. Exhibits to this Agreement (enumerated as follows):
    - 1) Contractor's Bid (pages 00 41 13-1 to 00 41 13-3, inclusive).
    - 2) Bid Schedule Unit Prices (Pages 00 41 43-1).
    - 3) Proposed Products Form (Page 00 43 33-1)
    - 4) Tabulation of Subcontractors (page 00 43 36-1).
    - 5) Documentation submitted by Contractor prior to Notice of Award (00 51 00-1)
  - i. The following which may be delivered or issued on or after the Effective Date of the Agreement and are not attached hereto:
    - 1) Notice to Proceed (Page 00 55 00-1).
    - 2) Change Orders.
- 2. The documents listed in Paragraph (a) Contents, are attached to this Agreement (except as expressly noted otherwise above).
- 3. There are no Contract Documents other than those listed above in this Article IV.

6/6/2019 00 52 13-3 Contract

## Project 19-16 Marquette Square Dumpster Enclosure Construction City of De Pere

IN WITNESS WHEREOF, the parties written above.	hereto have executed this Contract, the day and year f
(WITNESS)	(CONTRACTOR) (SEAL)
	BY:
(WITNESS)	
	(TITLE)
	BY:
	(TITLE)
	CITY OF DE PERE (SEAL)
Approved as to Form By:	(City Attorney)
Sufficient funds are available to provid	le for the payment of this obligation.  (COMPTROLLER)
BY:	BY:
(MAYOR)	BY:(CLERK-TREASURER)

## Project 19-16 Marquette Square Dumpster Enclosure Construction

## **SECTION 00 55 00**

## NOTICE TO PROCEED

Date:	
(CONTRACTOR NAME) (ADDRESS) (ADDRESS)	
PROJECT: (PROJECT NU	MBER AND NAME)
	nmence work in accordance with the CONTRACT dated ten (10) days of this Notice. All work under this contract shall (NUMBER IN WORDS) (_#) consecutive days from the star
of construction or	(NUMBER IN WORDS) (#) consecutive days from the star (DATE) whichever comes first.
	Department of Public Works  By: Eric P. Rakers, P.E. Title: City Engineer
	ACCEPTANCE OF NOTICE
Receipt of the above NOTICE	TO PROCEED is hereby acknowledged by
Company Name	, this day of, 20
Signature	
BY:	
Printed Name	
TITLE:	

## **Marquette Square Dumpster Enclosure Construction**

**SECTION 00 61 13** 

#### CITY OF DE PERE

#### **PAYMENT BOND**

KNOW ALL MEN BY THESE PRESENTS: That (CONTRACT	OR NAME), as Principal,		
hereinafter called Contractor, and			
as Surety, hereinafter called Surety, are held and firmly bound unt	to the City of De Pere, a municipal		
corporation of the State of Wisconsin, as Obligee, hereinafter call	ed the owner, for the use and benefit of		
claimants as herein below defined in the amount	(CONTRACT		
AMT. SPELLED OUT) (\$) for the payment where	eof Contractor and Surety bind		
themselves, their heirs, executors, administrators, successors and	assigns, jointly and severally, firmly by		
these presents.			
WHEREAS, Contractor has by written agreement dated	(date to be affixed by		
City) entered into a contract with City for Project (PROJECT NU	MBER), in accordance with drawings		
and specifications prepared by the Director of Public Works of sa	id City, which contract is by reference		
made a part hereof, and is hereinafter referred to as the CONTRACT.			

NOW, THEREFORE, THE CONDITION OF THIS OBLIGATION is such that, if Contractor shall promptly make payments to all claimants as hereinafter defined, for all labor and material used or reasonably required for use in the performance of the CONTRACT, then this obligation shall be null and void; otherwise it shall remain in full force and effect, subject, however, to the following conditions.

- 1. A claimant is defined as one having a direct contract with Contractor or with a sub-contractor of Contractor for labor, material, or both, used or reasonably required for use in the performance of the contract, labor and material being construed to include that part of water, gas, power, lights, heat, oil, gasoline, telephone service, or rental of equipment directly applicable to the contract.
- 2. The above named Contractor and Surety hereby jointly and severally agree with the City that every claimant as herein defined, who has not been paid in full before the expiration of a period of ninety (90) days after the date on which the last of such claimant's work or labor was done or performed, or materials were furnished by such claimant may sue on this bond for the use of such claimant in the name of the City, prosecute the suit to final judgment for such sum or sums as may be justly due claimant, and have execution thereon, provided, however, that the City shall not be liable for the payment of any costs or expenses of any such suit.
- 3. No suit or action shall be commenced hereunder by any claimant:
  - a. Unless claimant shall have given written notice to any two of the following: The Contractor, the City, or the Surety above named, within ninety (90) days after such claimant did or performed the last of the work or labor, or furnished the last of the materials for which said claim is made, stating with substantial accuracy the amount claimed and the name of the party to whom the materials were furnished, or for whom the work or labor was done or performed. Such notice shall be served by mailing the same by registered mail, postage prepaid, in an envelope addressed to the Contractor, City, or Surety, at any place where an office is regularly maintained for the transaction of business, or served in any manner in which legal process may be served in the State of Wisconsin, save that such service need not be made by a public officer.

6/6/2019 00 61 13-1 Payment Bond

## **Marquette Square Dumpster Enclosure Construction**

b. After the expiration of one (1) year following the date on which Contractor ceased work on said CONTRACT.

- c. Other than in a state court of competent jurisdiction in and for the County or other political subdivision of the state in which the project, or any part thereof, is situated, or in the United States District Court for the district in which the project, or any part thereof, is situated, and not elsewhere.
- 4. The amount of this bond shall be reduced by and to the extent of any payment or payments made in good faith hereunder, inclusive of the payment by Surety of mechanics' liens, which may be filed or recorded against said improvement, whether or not claim for the amount of such lien be presented under and against this bond.

SIGNED AND SEALED THIS	DAY OF	, 20	
In Presence of:			
(WITNESS)	(CONTRA	CTOR)	
(WITNESS)	(SURETY)		

## **Marquette Square Dumpster Enclosure Construction**

#### **SECTION 00 61 16**

#### **CITY OF DE PERE**

#### PERFORMANCE BOND

KNOW ALL MEN BY THESE PRESENTS: That (CONTRACTOR'S NAME), as Principal,
hereinafter called Contractor, and, as
Surety, hereinafter called Surety, are held and firmly bound unto the City of De Pere, a municipal
corporation of the State of Wisconsin, as Obligee, hereinafter called City, in the amount of
(AMOUNT WRITTEN OUT) (\$) for the payment whereof
Contractor and Surety bind themselves, their heirs, executors, administrators, successors and assign, jointly and severally, firmly by these presents.
WHEREAS, Contractor has by written agreement dated (date to be affixed by City) entered into a contract with the City for Project 19-16 in accordance with drawings and specifications prepared by the Director of Public Works of said City, which contract is by reference made a part hereof, and is hereinafter referred to as the CONTRACT.
NOW THEREFORE, THE CONDITION OF THIS OBLIGATION is such that, if the Contractor shall

it shall remain in full force and effect.

Whenever Contractor shall be, and declared by the City to be in default under the CONTRACT, the City

promptly and faithfully perform said CONTRACT, then this obligation shall be null and void; otherwise

having performed City's obligations there under, the Surety may promptly remedy the default, or shall promptly

- 1. Complete the CONTRACT in accordance with its terms and conditions or
- 2. Obtain a bid or bids for submission to City for completing the CONTRACT in accordance with its terms and conditions, and upon determination by the City and Surety of the lowest responsible bidder, arrange for a contract between such bidder and City make available as work progresses (even though there should be a default or succession of defaults under the contract or contracts of completion arranged under this paragraph) sufficient funds to pay the cost of completion less the balance of the contract price; but not exceeding, including other costs and damages for which the Surety may be liable hereunder, the amount set forth in the first paragraph hereof. The term "balance of the contract price" as used in this paragraph shall mean the total amount payable by City to Contractor under the CONTRACT and any amendments thereto, less the amount properly paid by City to Contractor.

6/6/2019 00 61 16-1 Performance Bond

## **Marquette Square Dumpster Enclosure Construction**

Any suit under this bond must be instituted before the expiration of two (2) years from the date on which final payment under the CONTRACT falls due. No right of action shall accrue on this bond to or for the use of any person or corporation other than the owner named herein or the heirs, executors, administrators or successors of City.

SIGNED AND SEALED THIS	DAY OF,	20
In the Presence of:		
(WITNESS)	(CONTRACTOR)	(SEAL)
(WITNESS)	(SURETY)	(SEAL)

## Marquette Square Dumpster Enclosure Construction Contractor's Application for Payment No.

	Application Perio	od:		Application Date: Contractor:	
	Owner: City of D	e Pere			
				Contractor's Project No.:	
APPLICATION F	FOR PAYMENT Change Order Sum	mary			
Approved Chang	ge Orders			RACT PRICE:	
Number	Additions	Deductions	<ol><li>CURRENT CONTR</li></ol>	RANGE Orders and Written Amendments (+ or -):	\$0.00 \$0.00 \$0.00
Fatal		20.00	a. Work Completed 100% of Contract	- Column H (5% up to 50% of Contract or 2.5% of	\$0.00
Total NET CHANGE E	Y CHANGE ORDERS:	o-	7. LESS PREVIOUS	.E TO DATE (Line 4 minus 5)	\$0.00 \$0.00 \$0.00
	S CERTIFICATION  d Contractor certifies that:(1)	all previous progress paym	Payment of:	\$ (Line 8 or other - attach explanation of other amount)	
applied on accoun connection wit all Work, materia isted in or cover	wner on account of Work don- unt to discharge Contractor's le th Work covered by prior Appl als and equipment incorporate red by this Application for Payr free and clear of all Liens, se	egitimate obligations incurro icaions for Payment; (2) title ed in said Work or otherwise ment will pass to Owner at	ed secommended by:	(Contractor)	(Date)
encumbrances ( ndemnifying Ow encumbrances);	except such as are covered by the ragainst any such Liens, sand (3) all Work covered by the the Contract Documents and	by a Bond acceptable to Ow ecurity interest or he Applicaton for Payment		\$ (Line 8 or other - attach explanation of other amount)	
Dv.6		IData:	is recommended by:	(Oursel)	(Data)
Зу:		Date:		(Owner)	(Date)

6/6/2019 00 62 76-1 Application for Payment

## City of De Pere

#### **SECTION 00 65 16**

## CERTIFICATE OF SUBSTANTIAL COMPLETION Project: Owner: Owner's Contract No.: Contractor: This [tentative] [definitive] Certificate of Substantial Completion applies to: □ All Work under the Contract Documents: □ The following specified portions of the Work: Date of Substantial Completion The Work to which this Certificate applies has been inspected by authorized representatives of Contractor and Engineer, and found to be substantially complete. The Date of Substantial completion of the Project or portion thereof designated above is hereby declared and is also the date of commencement of applicable warranties required by the Contract Documents, except as stated below A [tentative] [definitive] list of items to be completed or corrected is attached hereto. This list may not be all-inclusive, and the failure to include any items on such list does not alter the responsibility of the Contractor to complete all Work in accordance with the Contract Documents. The responsibilities between Owner and Contractor for security, operation, safety, maintenance, heat, utilities, insurance and warranties shall be as provided in the Contract Documents except as amended as follows: ☐ Not Amended ☐ Amended Responsibilities Owner's Amended Responsibilities: Contractor's Amended Responsibilities:

The following documents are attached to and made part of this Certificate:				
	eptance of Work not in accordance with the Contract or's obligation to complete the Work in accordance with			
Executed by Engineer	Date			
Accepted by Contractor	Date			

#### **SECTION 01 10 00**

#### **SUMMARY OF WORK**

#### PART 1 – GENERAL

## 1.1 SUMMARY

#### A. Section Includes

- 1. References
- 2. Work Covered by the Contract Documents
- 3. Work Sequence
- 4. Use of Premises
- 5. Warranty
- 6. Work By Others
- 7. Project Utility Sources
- 8. Miscellaneous Provisions

#### 1.2 REFERENCES

- A. General Specifications The work under this contract shall be in accordance with the City of De Pere, 2019 Construction Specifications and these Special Provisions and plans, and the latest edition of the Wisconsin Department of Transportation Standards Specifications for Highway and Structure Construction, where referenced in the City Specifications.
- B. Definitions. Any reference to the "state" or the "department" in said standard Specifications shall mean the "City of De Pere" for the purposes of this contract.

## C. Industry Standards

- 1. Unless the Contract Documents include more stringent requirements, applicable construction industry standards have the same force and effect as if bound or copied directly into the Contract Documents to the extent referenced. Such standards are made a part of the Contract Documents by reference.
- 2. Comply with standards in effect as of date of the Contract Documents, unless otherwise indicated.
- 3. If compliance with two or more standards is specified and the standards establish different or conflicting requirements for minimum quantities or quality levels, comply with the most stringent requirement.
- 4. The quantity or quality level shown or specified shall be the minimum provided or performed. The actual installation may comply exactly with the minimum quantity or quality specified, or it may exceed the minimum within reasonable limits. To comply with these requirements, indicated numeric values are minimum or maximum, as appropriate, for the context of requirements.
- 5. Each section of the specifications generally includes a list of reference standards normally referred to in that respective section. The purpose of this list is to furnish the Contractor with a list of standards normally used for outlining the

6/6/2019 01 10 00-1 Summary of Work

## **Marquette Square Dumpster Enclosure Construction**

quality control desired on the project. The lists are not intended to be complete or all inclusive, but only a general reference of standards that are regularly referred to.

6. Each entity engaged in construction on the Project shall be familiar with industry standards applicable to it construction activity. Copies of applicable standards are not bound with the Contract Documents. Where copies of standards are needed to perform a required construction activity, obtain copies directly from the publication source and make them available on request.

#### 1.3 WORK COVERED BY THE CONTRACT DOCUMENTS

- A. Project Identification
  - 1. Project Location
    - a. Marquette Square Parking Lot
  - 2. Work will be performed under the following prime contract:
    - a. Project 19-16 Marquette Square Dumpster Enclosure Construction
- B. The Work includes:
  - 1. Dumpster Enclosure Construction

## 1.4 WORK SEQUENCE

- A. Conduct construction activities to maintain access to businesses throughout construction.
- B. All work under this project shall be completed by Friday, November 1, 2019.

## 1.5 USE OF PREMISES

- A. Contractor shall have full use of the premises for construction operations, including use of the Project Site, as allowed by law, ordinances, permits, easement agreements and the Contract documents.
- B. Contractor's use of premises is limited only by Owner's right to perform work or to retain other contractors on portions of the Project.
- C. The Project Site is limited to property boundaries, rights-of-way, easements, and other areas designated in the Contract Documents.
- D. Provide protection and safekeeping of material and products stored on or off the premises.
- E. Move any stored material or products which interfere with operations of Owner or other Contractors.

6/6/2019 01 10 00-2 Summary of Work

# 1.6 WARRANTY

- A. The Contractor warrants and guarantees to the City that all work shall be in accordance with the Contract Documents and will not be defective. Prompt notice of all defects will be given to the Contractor. All defective work, whether or not in place, may be rejected, corrected or accepted as provided in this proposal.
- B. If within one (1) year after the date of contract work completion or such longer period of time as may be prescribed by law or by the terms of any applicable special guarantee required by the Contract Documents or by a special provision of the Contract Documents, any work is found to be defective, the Contractor shall comply in accordance with the City's written instructions. These written instructions will include either correcting such defective work or, if it has been rejected by the City, removing it from the site and replacing it with non-defective work. If the Contractor does not promptly comply with the terms of such instructions, or in an emergency where delay would cause serious risk or loss or damage, the City may have the defective work corrected or the rejected work removed and replaced. All direct and indirect costs of correction or removal and replacement of defective work, including compensation for additional professional services, shall be paid by the Contractor.

# 1.7 WORK BY OTHERS

- A. Cooperate fully with separate contractors and/or Owner so work by others may be carried out smoothly, without interfering with or delaying work under this Contract.
- B. Asphalt paving and pavement marking is to be completed by others. The City will maintain all base aggregate after construction is completed and approved until the asphalt restoration occurs. Asphalt paving will occur under the City contract 19-07 Asphalt, Curb and Sewer Repair.

# 1.8 PROJECT UTILITY SOURCES

- A. Green Bay Metropolitan Sewer District (NEW Water), Lisa Sarau, (<u>lsarau@newwater.us</u>) (920-438-1039)
- B. AT&T, Shea Gorzelanczyk, (<u>sg2528@att.com</u>) (920-433-4250)
- C. Wisconsin Public Service, Bob Laskowski, (<u>rtlaskowski@wisconsinpublicservice.com</u>) (920-617-2775)
- D. Charter, Vince Albin, (vince.albin@charter.com) (920-378-0444)
- E. Nsight, Rick Vincent, (rick.vincent@nsight.com) (920-617-7316)
- F. TDS Metrocom, Steve Jakubiec, (steve.jakubiec@tdstelecom.com) (920-882-4166)

6/6/2019 01 10 00-3 Summary of Work

# **Marquette Square Dumpster Enclosure Construction**

- G. Net-Lec (Mi-Tech Services), Dennis Lafave, (<u>dlafave@mi-tech.us</u>) (920-619-9774)
- H. Level3 (Mi-Tech Services), Chris Kraus, (ckraus@mi-tech.us) (414-550-6201)
- I. Central Brown County Water Authority, Rob Michaelson, (<u>rmichaelson@mpu.org</u>) (920-686-4354)

# 1.9 MISCELLANEOUS PROVISIONS

- A. Notification to businesses The Contractor shall individually notify all businesses 2-weeks prior to the start of operations, giving an estimated time that vehicle movement will be limited or prohibited. Property owners shall be notified 24-hours prior to closing a drive.
- B. Disturbed areas between the enclosure and the existing asphalt concrete shall be brought to grade with crushed aggregate base course.
- C. Access to the Site shall be off of N. Wisconsin Street. Trucks entering from the north should use George Street or the roundabout at S. Broadway Street and Main Avenue to access N. Wisconsin Street.
- D. Access to adjacent parking stalls, not located within the designated work zone shall be maintained throughout the duration of work.

PART 2 – PRODUCTS

PART 3 – EXECUTION

END OF SECTION

6/6/2019 01 10 00-4 Summary of Work

# **SECTION 01 22 02**

# MEASUREMENT AND PAYMENT STORM SEWER

#### PART 1 – GENERAL

# 1.1 SUMMARY

A. Section includes:

Bid Item No.

1. Catch Basins/Inlets

ST-01

#### B. Unit Prices include:

- 1. Defined work for each Unit Price Item which will provide a functionally complete Project when combined with all unit price items. If there are specific work items which the Contractor believes are not identified in any Unit Price Item, but is required to provide a functionally complete Project, then the identified specific work items shall be included in the appropriate Unit Price Item.
- 2. The method of measurement for payment.
- 3. The price per unit for payment.

#### 1.2 GENERAL WORK ITEMS

- A. Include with the appropriate Unit Price Item the following work items which are common to the Unit Price Items for storm sewer systems.
- B. If there is a specific Unit Price Item for any of the following items, then the work item shall be included with that specific unit price item.
  - 1. Traffic Control.
  - 2. Sawcutting asphalt and/or concrete.
  - 3. Removal, hauling and disposal of surface materials including road pavement, curb and gutter, sidewalk, driveways and other pavement surfaces in the trench area and as shown on the drawings.
  - 4. Dewatering.
  - 5. Excavation.
  - 6. Open trench installation method (unless bid item specifies other method).
  - 7. Pipe bedding.
  - 8. Backfilling and compacting native obtained from the excavation.
  - 9. Supplying, hauling, backfilling and compacting granular material.
  - 10. Loading, hauling and disposing of surplus excavated material.
  - 11. Landscaping turf establishment surface restoration and trees and bushes damaged during construction.

- 12. Maintenance, protection, replacement and/or repair of facilities not designated for alteration on the Site beyond the limits identified.
- 13. Site access requirements including temporary aggregate material as required for local traffic access.
- 14. Bulkhead and abandoned existing storm sewer with flowable fill as shown on Drawings.
- 15. If crossing or undermining of existing public or private utility, then include:
  - a. Maintaining the utility in service.
  - b. Replacing of existing utilities, if damaged.
  - c. Providing support and bedding material.
- 16. Dust control.
- 17. Remove and replace existing mailboxes and traffic signs.
- 18. Restroom facilities
- 19. Easement and right-of-way requirements.
- 20. Construction staking and other survey work not provide by the Engineer.
- 21. Regulatory requirements.
- 22. Preconstruction videotaping and video equipment.
- 23. Quality assurance and quality control testing and inspections.
- 24. Shop drawings and other submittals.

#### 1.3 CATCH BASIN/INLETS

- A. The unit price for Catch Basin/Inlet work includes:
  - 1. General Work Items of Article 1.2.
  - 2. Precast reinforced concrete components.
  - 3. Joint flexible gasket material.
  - 4. Grout seal between the catch basin/inlet structure and the sewer pipe.
  - 5. Adjusting rings grouted in place.
  - 6. Casting frame and grate.
  - 7. Bedding material.
  - 8. Supply and install six to 10 feet of four-inch flexible perforated plastic pipe with geotextile wrap subgrade drain.
  - 9. Sand fill and Class "B" concrete floor with flow line.
  - 10. Temporary cover over catch basin/inlet to prevent eroded materials from entering.
  - 11. Final casting adjustment.
  - 12. Sawing existing storm sewer.
  - 13. Sewer pipe stub with connections to existing storm pipe.
- B. Measurement for payment will be the actual number installed.
- C. The unit of measurement for payment is each.

# END OF SECTION

# **SECTION 01 22 04**

# MEASUREMENT AND PAYMENT STREET AND DRAINAGE CONSTRUCTION

# PART 1 – GENERAL

# 1.1 SUMMARY

A.	Sec	ction includes:	Bid Item No.
	1.	Remove Curb & Gutter	SD-01
	2.	Portland Cement Concrete Curb & Gutter	SD-02
	3.	Drilling Tie Bars	SD-03
	4.	Topsoil Landscaping	SD-04

#### B. Unit Prices include:

- 1. Defined work for each Unit Price Item which will provide a functionally complete Project when combined with all unit price items. If there are specific work items which the Contractor believes are not identified in any Unit Price Item, but is required to provide a functionally complete Project, then the identified specific work items shall be included in the appropriate Unit Price Item.
- 2. The method of measurement for payment.
- 3. The price per unit for payment.

# 1.2 GENERAL WORK ITEMS

- A. Include with the appropriate Unit Price Item the following work items which are common to the Unit Price Items for street and drainage systems.
- B. If there is a specific Unit Price Item for any of the following items, then the work item shall be included with that specific unit price item.
  - 1. Traffic Control.
  - 2. Sawcutting asphalt and/or concrete.
  - 3. Removal, hauling and disposal of surface materials including road pavement, curb and gutter, sidewalk, driveways and other pavement surfaces in the trench area and as shown on the drawings.
  - 4. Maintenance, protection, replacement and/or repair of facilities not designated for alteration on the Site.
  - 5. Site access requirements including temporary aggregate material as required for local traffic access.
  - 6. Dust control.
  - 7. Remove and replace existing mailboxes and traffic signs.

- 8. Restroom facilities.
- 9. Construction staking and other survey work not provide by the Owner.
- 10. Regulatory requirements.
- 11. Quality assurance and quality control testing and inspections.
- 12. Final casting and valve box adjustment.
- 13. Shop drawings and other submittals.

# 1.3 REMOVE CURB & GUTTER

- A. The unit price for Remove Curb & Gutter work includes:
  - 1. General Work Items of Article 1.2.
  - 2. Sawcutting, breaking, and removal of existing concrete curb and gutter at the locations specified by the Engineer or designated on the plan sheets.
  - 3. Sawcutting to protect adjacent curb and gutter or pavement surfaces.
- B. Measurement for payment will be along the flow line of the gutter and through inlets/catch basins.
- C. The unit of measurement for payment is linear feet.

# 1.4 PORTLAND CEMENT CONCRETE CURB & GUTTER

- A. The unit price for Portland Cement Concrete Curb & Gutter work includes:
  - 1. General Work Items of Article 1.2.
  - 2. Providing Portland Cement concrete mixture of size shown in the drawing or specified elsewhere.
  - 3. Providing expansion joints.
  - 4. Providing curing.
  - 5. Subgrade preparation.
  - 6. Provide crushed aggregate base.
  - 7. Fine grading of subgrade.
  - 8. Providing contraction joints.
  - 9. Driveway entrances and handicap ramp entrances.
  - 10. Adjustment of catch basin/inlets.
  - 11. Finishing
  - 12. Protection.
  - 13. Restoration behind curb.
  - B. Measurement for payment will be along the flow line of the gutter through inlets/catch basins.
  - C. The unit of measurement for payment is linear feet.

# 1.5 DRILLING TIE BARS

- A. The unit price for Drilling Tie Bars and Dowel Bars work includes:
  - 1. General Work Items of Article 1.2.
  - 2. Providing and installing tie bars and dowel bars, including coating.
  - 3. For drilling holes in concrete not placed under the contract.
  - 4. For epoxying or driving.
- B. Measurement for payment will be the actual number of bars installed.
- C. The unit of measurement for payment is each.

# 1.6 TOPSOIL LANDSCAPING

- A. The unit price for Landscaping-Topsoil, Seed, Fertilize, and Mulch work includes:
  - 1. General Work Items of Article 1.2.
  - 2. Provide 4" topsoil or salvaged topsoil.
  - 3. Provide seed.
  - 4. Provide fertilizer.
  - 5. Provide mulch.
  - 6. Provide maintenance.
- B. Measurement for payment will be the width and length not greater than the road right of way, not greater than the easement and not greater than 15 feet beyond the top of either side of ditches outside the right of way.
- C. The unit of measurement for payment is square yard.

# **END OF SECTION**

#### **SECTION 01 22 05**

# MEASUREMENT AND PAYMENT SPECIAL CONSTRUCTION

# PART 1 – GENERAL

# 1.1 SUMMARY

A. Section includes: Bid Item No.

- 1. Dumpster Enclosure Construction and Restoration
- 2. Remove Tree and Grind Stump

SP-01 SP-02

# B. Unit Prices include:

- 1. Defined work for each Unit Price Item which will provide a functionally complete Project when combined with all unit price items. If there are specific work items which the Contractor believes are not identified in any Unit Price Item, but is required to provide a functionally complete Project, then the identified specific work items shall be included in the appropriate Unit Price Item.
- 2. The method of measurement for payment.
- 3. The price per unit for payment.

# 1.2 GENERAL WORK ITEMS

- A. Include with the appropriate Unit Price Item the following work items which are common to the Unit Price Items for special construction.
- B. If there is a specific Unit Price Item for any of the following items, then the work item shall be included with that specific unit price item.
  - 1. Traffic Control.
  - 2. Loading, hauling and disposing of surplus material.
  - 3. Maintenance, protection, replacement and/or repair of facilities not designated for alteration on the Site beyond the limits identified.
  - 4. Dust control.
  - 5. Restroom facilities.
  - 6. Construction staking and other survey work not provide by the Engineer.
  - 7. Regulatory requirements.
  - 8. Quality assurance and quality control testing and inspections.
  - 9. Shop drawings and other submittals.
  - 10. Saw-cutting of existing asphaltic concrete pavements.
  - 11. Removals of existing asphaltic concrete pavements.
  - 12. Crushed aggregate base course placement in disturbed areas to bring surfaces to grade.

# 1.3 DUMPSTER ENCLOSURE CONSTRUCTION AND RESTORATION

- A. The unit price for Dumpster Enclosure Construction work includes:
  - 1. Unclassified excavation
  - 2. Construction of 6'-8" enclosure wall consisting of split-faced concrete masonry units with eight-inch by eight-inch bond beam.
  - 3. Construction of eight-inch reinforced concrete slab with integral 12-inch by 12-inch footing and two #4 bars continuous at perimeter.
  - 4. Construction of concrete filled galvanized steel pipe gate posts
  - 5. Construction of tube steel welded form gate frames
  - 6. Construction of 18-inch diameter gate post footings
  - 7. Installation of all gate hinges, hasps, cane bolts, and corresponding holes in concrete for cane bolts
  - 8. Construction and installation of 18-foot gate with vinyl fencing accents
  - 9. Construction and installation of 5-foot gate with vinyl fencing accents
  - 10. Construction and installation of 4-foot access with vinyl fencing accents
  - 11. Construction of 2-inch by 8-inch concrete wall cap
  - 12. Placement of crushed aggregate base course
  - 13. Grading of aggregate base course and other unclassified base materials
  - 14. Installation of a maximum of four type-D inlet protection
  - 15. Installation of brick masonry and corresponding concrete and steel reinforcement.
  - 16. Mortar for brick masonry work
  - 17. Wetting of bricks and blocks
- B. Measurement of payment will not be made.
- C. The unit of measurement for payment is lump sum.

#### 1.4 REMOVE TREE AND GRIND STUMP

- A. The unit price for Remove Tree and Grind Roots work includes:
  - 1. General Work Items of Article 1.2.
  - 2. Cutting and dispose of trees.
  - 3. Removing and disposing of stump.
- B. Measurement and payment will be the will be the inch diameter of trees removed.
- C. The unit of measurement for payment is inch diameter.

# **END OF SECTION**

#### **SECTION 01 29 00**

# PAYMENT PROCEDURES

# PART 1 – GENERAL

# 1.1 SUMMARY

#### A. This section includes:

1. Administrative and procedural requirements necessary to prepare and process Applications for Payment

# 1.2 SCHEDULE OF VALUES

A. Unit Price work will be the Schedule of Values used as the basis for reviewing Applications for Payment.

# 1.3 APPLICATIONS FOR PAYMENT

- A. Each Application for Payment shall be consistent with previous applications and payments as recommended by the Engineer and approved by Owner.
- B. The date for each progress payment should be the 3rd Tuesday of each month. The period covered by each Application for Payment starts on the day following the end of the preceding period and ends the 4<sup>th</sup> Friday of the Month.
- C. Use forms provided by Engineer for Applications for Payment. Sample copy of the Application for Payment and Continuation Sheet is included in Section 00 62 76.

# D. Application Preparation Procedures

- 1. When requested by the Contractor, the Engineer will determine the actual quantities and classifications of Unit Price Work performed.
  - a. Preliminary determinations will be reviewed with the Contractor before completing Application for Payment.
  - b. Engineer will complete the Application for Payment based on Engineer's decision on actual quantities and classifications.
  - c. Engineer will submit three original copies of Application for Payment to Contractor for certification of all three original copies.
  - d. Contractor shall submit signed Application for payment to Owner for approval within time frame agreed to at the Preconstruction Conference.
- 2. If payment is requested for materials and equipment not incorporated in the Work, then the following shall be submitted with the Application for Payment:
  - a. Evidence that materials and equipment are suitably stored at the site or at another location agreed to in writing.
  - b. A bill of sale, invoice, or other documentation warranting that the materials and equipment are free and clear of all liens.

6/6/2019 01 29 00-1 Payment Procedures

# **Marquette Square Dumpster Enclosure Construction**

- c. Evidence that the materials and equipment are covered by property insurance.
- 3. Complete every entry on form. Execute by a person authorized to sign legal documents on behalf of Contractor.
- E. With each Application for Payment, submit waivers of liens from subcontractors and suppliers for the construction period covered by the previous application.
  - 1. Submit partial waivers on each item for amount requested before deduction for retainage on each item.
  - 2. When an application shows completion for an item, submit final or full waivers.
  - 3. Owner reserves the right to designate which entities involved in the Work shall submit waivers.
  - 4. Submit final Application for Payment with or preceded by final waivers from every entity involved with performance of the Work covered by the application.
  - 5. Submit waivers of lien on forms executed in a manner acceptable to Owner.
- F. The following administrative actions and submittals shall precede or coincide with submittal of first Application for Payment:
  - 1. List of subcontractors.
  - 2. Schedule of Values (For Lump Sum Work).
  - 3. Contractor's construction schedule.
- G. Submit final Application for Payment with releases and supporting documentation not previously submitted and accepted including, but not limited, to the following:
  - 1. Evidence of completion of Project closeout requirements.
  - 2. Insurance certificates for products and completed operations where required and proof that taxes, fees, and similar obligations were paid.
  - 3. Updated final statement, accounting for final changes to the Contract Sum.
  - 4. Consent of Surety to Final Payment.
  - 5. Final lien waivers as evidence that claims have been settled.
  - 6. Final liquidated damages settlement statement.

PART 2 – PRODUCTS

PART 3 – EXECUTION

END OF SECTION

6/6/2019 01 29 00-2 Payment Procedures

# **SECTION 01 32 33**

# CONSTRUCTION PHOTOGRAPHS

# PART 1 – GENERAL

# 1.1 SUMMARY

- A. Section Includes:
  - 1. Photographs for utility construction sites.

# 1.2 SUBMITTALS

A. Submit electronic files of each photographic view within seven (7) days of taking photographs.

# 1.3 QUALITY ASSURANCE

A. Photographs are to be submitted to the Engineer for approval prior to the start of construction.

#### PART 2 – PRODUCTS

#### PART 3 – EXECUTION

# 3.1 UTILITY AND STREET CONSTRUCTION SITES

- A. Prior to start of construction provide sufficient photographs to adequately show the existing facilities and conditions within and adjacent to the construction Site to serve as a guide for final restoration including:
  - 1. Roads including shoulders and/or curb and gutter.
  - 2. Sidewalks, parking areas, and driveways.
  - 3. Utility structures.
  - 4. Landscaping including signs, plantings, walls, fences, trees, shrubbery, etc.
  - Mail boxes.
  - 6. Drainage facilities including culverts, inlets, ditches.
  - 7. Building structures.
- B. During construction provide sufficient photographs (a minimum of one per 100 feet of installed utility) to adequately show construction means, methods, and Site conditions including:
  - 1. Crossings of other utilities.
  - 2. Exposure of existing structures.
  - 3. Soil conditions.

#### END OF SECTION

6/6/2019 01 32 33-1 Construction Photographs

# **SECTION 01 33 00**

# **SUBMITTALS**

# PART 1 – GENERAL

# 1.1 SUMMARY

- A. Section includes administrative and procedural requirements for submittals:
  - 1. Progress Schedule
  - 2. Schedule of Shop Drawings and Sample Submittals
  - 3. Shop Drawings
- B. Failure to meet Submittal requirements to the satisfaction of the Engineer will constitute unsatisfactory performance of the work in accordance with the Contract Documents, therefore, the Engineer may recommend to the Owner that all or a portion of payments requested during the corresponding pay period be withheld until these requirements are met.

# 1.2 SUBMITTAL PROCEDURES

- A. Coordination: Transmit each submittal sufficiently in advance of performance of related construction activities to avoid delay.
  - 1. Coordinate each submittal with fabrication, purchasing, testing, delivery, other submittals, and related activities that require sequential activity.
  - 2. Coordinate transmittal of different types of submittals for related elements of the work so processing will not be delayed by the need to review submittals concurrently for coordination.
    - a. The Engineer reserves the right to withhold action on a submittal requiring coordination with other submittals until all related submittals are received.
  - 3. To avoid the need to delay installation as a result of the time required to process submittals, allow sufficient time for submittal review, including time for resubmittals.
    - a. Allow two weeks for initial submittal.
    - b. Allow two weeks for reprocessing each submittal.
    - c. No extension of Contract Time will be authorized because of failure to transmit submittals to the Engineer sufficiently in advance of the work to permit processing.
- B. Submittal Preparation: Place a permanent label or title block on each submittal for identification. Indicate the name of the entity that prepared each submittal on the label or title block.
  - 1. Assign a reference number to each submittal and re-submittal.
  - 2. Provide a space approximately 4 by 5 inches (100 by 125 mm) on the label or beside the title block on Shop Drawings to record the Contractor's review and approval markings and the action taken.

6/6/2019 01 33 00-1 Submittals

# **Marquette Square Dumpster Enclosure Construction**

3. Include the following information on the label for processing and recording action taken.

- a. Project name.
- b. Date.
- c. Name and address of the Engineer.
- d. Name and address of the Contractor.
- e. Name and address of the subcontractor.
- f. Name and address of the supplier.
- g. Name of the manufacturer.
- h. Number and title of appropriate Specification Section.
- i. Drawing number and detail references, as appropriate.
- 4. Each submittal shall be stamped by the Contractor indicating that submittal was reviewed for conformance with the Contract Documents. The Engineer will not accept unstamped submittals.
- C. Submittal Transmittal: Package each submittal appropriately for transmittal and handling. Transmit each submittal to the Engineer. The Engineer will not accept submittals received from sources other than the Contractor.
  - 1. On the transmittal, record relevant information and requests for Engineer action. On a form, or separate sheet, record deviations from Contract Document requirements, including variations, limitations, and justifications. Include Contractor's certification that information complies with Contract Document requirements.

# 1.3 CONTRACTOR'S PROGRESS SCHEDULE

- A. Prepare and submit to the Engineer within 10 days after the Effective Date of the Agreement, four copies of a preliminary progress schedule of the work activities from Notice to Proceed until Substantial Completion.
  - 1. Provide sufficient detail of the work activities comprising the schedule to assure adequate planning and execution of the work, such that in the judgment of the Engineer, it provides an appropriate basis for monitoring and evaluation of the progress of the work. A work activity is defined as an activity which requires substantial time and resources (manpower, equipment, and/or material) to complete and must be performed before the contract is considered complete.
  - 2. The schedule shall indicate the sequence of work activities. Identify each activity with a description, start date, completion date and duration. Include, but do not limit to the following items, as appropriate to this contract:
    - a. Shop drawing review by the Engineer.
    - b. Excavation and grading.
    - c. Asphalt and concrete placement sequence.
    - d. Restoration.
    - e. Construction of various segments of utilities.
    - f. Subcontractor's items of work.
    - g. Allowance for inclement weather.
    - h. Contract interfaces, date of Substantial Completion.

6/6/2019 01 33 00-2 Submittals

# **Marquette Square Dumpster Enclosure Construction**

- i. Interfacing and sequencing with existing facilities and utilities.
- j. Sequencing of major construction activities.
- k. Milestones and completion dates.
- B. Distribution: Following response to the initial submittal, print and distribute copies of the revised construction schedule to the Engineer, Subcontractors, and other parties required to comply with scheduled dates. When revisions are made, distribute to the same parties. Delete parties from distribution when they have completed their assigned portion of the work and are no longer involved in construction activities.
- C. Schedule Updating: Revise the schedule after each meeting, event, or activity where revisions have been recognized or made. Issue the updated schedule concurrently with the report of each meeting.
- D. Punch List: Prepare and submit to the Engineer within 10 days after substantial completion a detailed progress schedule for outstanding work and punch list items.

# 1.4 SCHEDULE OF SHOP DRAWINGS AND SAMPLE SUBMITTALS

- A. Submit four (4) hard copies or electronic copies of preliminary submittal schedule in accordance with the General Conditions of the Contract and as follows:
  - 1. Coordinate submittal schedule with the subcontractors, Schedule of Values, and of products as well as the Contractor's Progress Schedule.
  - 2. Prepare the schedule in chronological order. Provide the following information:
    - a. Scheduled date for the first submittal.
    - b. Related Section number.
    - c. Submittal category (Shop Drawings, Product Data, or Samples).
    - d. Name of the subcontractor.
    - e. Description of the part of the work covered.
    - f. Scheduled date for the Engineer's final release or approval.
- B. Distribution: Following response to the preliminary submittal schedule, print and distribute copies of the revised submittal schedule to the Engineer, Owner, subcontractors, and other parties required to comply with submittal dates indicated. Post copies in the field office.
  - 1. When revisions are made, distribute to the same parties and post in the same locations. Delete parties from distribution when they have completed their assigned portion of the work and are no longer involved in construction activities.
- C. Schedule Updating: Revise the schedule after each meeting or activity where revisions have been recognized or made. Issue the updated schedule concurrently with the report of each meeting.

6/6/2019 01 33 00-3 Submittals

# 1.5 SHOP DRAWINGS

- A. Submit newly prepared information drawn accurately to scale. Highlight, encircle, or otherwise indicate deviations from the Contract Documents. Do not reproduce Contract Documents or copy standard information as the basis of Shop Drawings. Standard information prepared without specific reference to the Project is not a Shop Drawing.
- B. Collect product data into a single submittal for each element of construction of system.
  - Product data includes printed information, such as manufacturer's installation instructions, catalog cuts, standard color charts, roughing-in diagrams and templates, standard wiring diagrams, and performance curves.
  - 1. Mark each copy to show actual product to be provided. Where printed Product Data includes information on several products that are not required, mark copies to indicate the applicable information. Include the following information:
    - a. Manufacturer's printed recommendations.
    - b. Compliance with trade association standards.
    - c. Compliance with recognized testing agency standards.
    - d. Application of testing agency labels and seals.
    - e. Notation of dimensions verified by field measurement.
    - f. Notation of coordination requirements.
- C. Do not use shop drawings without an appropriate final stamp indicating action taken.
- D. Submittals: Submit four (4) copies of each required submittal. The Engineer will retain two copies, and return the others to the Contractor marked with action taken and corrections or modifications required.
- E. Distribution: Furnish copies of reviewed submittal to installers, subcontractors, suppliers, manufacturers, fabricators, and others required for performance of construction activities. Show distribution on transmittal forms. Maintain one copy at the project site for reference.
  - 1. Do not proceed with installation until a copy of the Shop drawing is in the installer's possession.
  - 2. Do not permit use of unmarked copies of the Shop Drawing in connection with construction.

# 1.6 ENGINEER'S ACTION

A. Except for submittals for the record or information, where action and return is required, the Engineer will review each submittal, mark to indicate action taken, and return promptly. The Engineer will stamp each submittal with a uniform action stamp. The Engineer will mark the stamp appropriately to indicate the action taken, as follows:

6/6/2019 01 33 00-4 Submittals

# **Marquette Square Dumpster Enclosure Construction**

- 1. "No Exceptions Taken": The work covered by the submittal may proceed provided it complies with notations or corrections on the submittal and requirements of the Contract Documents.
- 2. "Make Corrections Noted": The work covered by the submittal may proceed provided it complies with notations or corrections on the submittal and requirements of the Contract Documents.
- 3. "Amend and Resubmit": Do not proceed with work covered by the submittal. Resubmit without delay. Do not use, or allow others to use, submittals marked "Amend and Resubmit" at the Project Site or elsewhere where work is in progress.
- 4. "Rejected See Remarks": Do not proceed with work covered by the submittal. Resubmit without delay. Do not use, or allow others to use, submittals marked "Rejected and Resubmit" at the Project Site or elsewhere where work is in progress.
- B. Unsolicited Submittals: The Engineer/Architect will return unsolicited submittals to the sender without action.

PART 2 – PRODUCTS

PART 3 – EXECUTION

**END OF SECTION** 

6/6/2019 01 33 00-5 Submittals

#### **SECTION 01 41 00**

# **REGULATORY REQUIREMENTS**

# PART 1 – GENERAL

#### 11 SUMMARY

- A. Section Includes
  - 1. Underground Utilities
  - 2. Property Monuments
  - 3. Traffic Control

# 1.2 UNDERGROUND UTILITIES

A. Under the provisions of Wisconsin Statutes, Section 182.0175, all contractors, subcontractors, and any firm or individual intending to do work on this contract shall contact all utility firms in the affected area of construction a minimum of three (3)working days prior to beginning construction so that affected utilities will be located and marked.

# 1.3 PROPERTY MONUMENTS

- A. Protect iron pipe monuments from movement.
- B. The cost of replacement of any monuments moved or destroyed during construction shall be the Contractor's responsibility.
- C. Perpetuation of destroyed or moved monuments shall be performed in accordance with state statutes by a registered land surveyor.

# 1.4 TRAFFIC CONTROL

- A. Provide traffic control facilities including barricades, signs, lights, warning devices, pavement markings, flaggers, etc.
- B. Construct and use traffic control facilities in accordance with the U.S. D. O. T. Federal Highway Administration's Manual on Uniform Traffic Control Devices for Streets and Highways.
- C. Maintain traffic control devices as required to properly safeguard the public travel through final completion, including during periods of suspension of work.

PART 2 – PRODUCTS (Not used)

PART 3 – EXECUTION (Not used)

END OF SECTION

6/6/2019 01 41 00-1 Regulatory Requirements

# **SECTION 01 71 23**

# FIELD ENGINEERING

# PART 1 – GENERAL

# 1.1 SUMMARY

- A. Section Includes
  - 1. Engineering Surveys Provided by the Engineer
  - 2. Engineering Surveys Provided by the Contractor

# 1.2 SUBMITTALS

A. None

PART 2 – PRODUCTS (Not Used)

# PART 3 – EXECUTION

# 3.1 PREPARATION

- A. Investigate and verify the existence and location of site improvements, utilities, and other existing facilities.
- B. Before construction, verity the location of invert elevations at points of connection of sanitary sewer, storm sewer, water piping and underground electrical services.
- C. Furnish information to the Engineer and the appropriate utility regarding conflicts that are necessary to adjust, move, or relocate existing utility structures, utility poles, lines, services, or other utility appurtenances located in or affected by construction.
- D. Provide the Engineer two working days advance notification when ready for engineering surveys for construction to be provided by the Engineer.

# 3.2 ENGINEERING SURVEYS TO BE PROVIDE BY THE ENGINEER

#### A. General

- 1. Establish benchmarks for construction as shown on the drawings.
- 2. Establish control points as shown on the drawings.

# 3.3 ENGINEERING SURVEYS TO BE PROVIDED BY THE CONTRACTOR

#### A. General

1. Locate, preserve and protect established construction reference stakes, benchmarks and control points.

# **Marquette Square Dumpster Enclosure Construction**

- 2. Locate, preserve and protect property corners and section corner monuments. If moved or destroyed due to Contractor negligence, then replace in accordance with state requirements; some of which are referenced in the "Regulatory Requirements".
- 3. Provide additional construction staking as necessary to complete construction based on the construction reference stakes provided by the Engineer and the Drawings.
- 4. Before beginning with necessary construction staking, verify the information shown on the Drawings, in relation to the established construction reference stakes, bench marks, control points and property corners. Notify the Engineer of any discrepancies.
- 5. Remove construction reference stakes when directed by the Engineer.

END OF SECTION

6/6/2019 01 71 23-2 Field Engineering

#### **SECTION 04 22 00**

# **CONCRETE UNIT MASONRY**

# PART 1 – GENERAL

# 1.1 SUMMARY

#### A. Section Includes

1. Non-loadbearing burnished concrete masonry units

#### 1.2 REFERENCES

- A. Comply with the following industry standards:
  - 1. American Society for Testing Materials (ASTM)
  - 2. International Building Code (IBC)
  - 3. Masonry Standards Joint Committee (MSJC)
  - 4. National Concrete Masonry Association (NCMA): TEK Manual for Concrete Masonry Design and Construction
  - 5. American Concrete Institute (ACI): ACI 117 Specification for Tolerances for Concrete Construction and Materials

# 1.3 SUBMITTALS

# A. Product Data:

- 1. Manufacturer's data sheets on each product to be used including:
  - i. Storage and handling requirements and recommendations
  - ii. Installation methods
  - iii. Cleaning and maintenance instructions
- 2. Certificate of compliance to specified performance requirements
- 3. Verification samples: for each product specified two samples, representing types, colors, textures, and finishes to be installed.

# 1.4 DELIVERY, STORAGE & HANDLING

- A. Deliver, store and handle materials and products in strict compliance with manufacturer's instructions and recommendations. Stack cubes of brick only one cube high. Protect from damage.
- B. Delivery: Deliver Architectural CMUs in manufacturer's unopened, labeled packaging. Units shall be inspected upon delivery. Defective units shall be removed immediately.

6/6/2019 04 22 00-1 Concrete Unit Masonry

- C. Storage: Store materials off the ground and keep free from groundwater, soil contamination, mud, and dust. Materials shall be protected from precipitation and harmful weather conditions. Product with visible frozen moisture shall not be installed.
- D. Handling: Units shall be handled in a manner that prevents breakage and damage.

# 1.7 PROJECT/SITE CONDITIONS

- A. Environmental Requirements:
  - 1. Protect CMUs from rain and freezing temperatures prior to, during, and for 48 hours after installation of materials.
  - 2. When ambient temperature is below 40 degrees F (4.4 degrees C) or exceeds 90 degrees F (32.2 degrees C), comply with requirements for project conditions in accordance with MSJC Specification for Masonry Structures including the following:
    - i. Par. 1.8 C. Cold Weather Construction
    - ii. Par. 1.8 D. Hot Weather Construction
  - 3. Do not continue masonry construction during heavy rains, as partially set or plastic mortar is susceptible to washout until 8 to 24 hours of curing occurs (depending upon environmental conditions).
  - 4. When rain is likely, cover construction materials. Newly constructed masonry shall be protected from rain by draping a weather-resistant covering over the assembly. The cover shall be secured in place and extend over mortar that is susceptible to washout.

# PART 2 – PRODUCTS

# 2.1 MANUFACTURERS

- A. Acceptable Manufacturer: County Materials Corporation, which is located at: 205 North St. P.O. Box 100; Marathon, WI 54448-0100; Toll Free Tel: 800-289-2569; Tel: 715-848-1365; Fax: 715-443-3691; Email: request info (info@countymaterials.com); Web: www.countymaterials.com
- B. Engineer Approved Equal

# 2.2 CONCRETE MASONRY UNITS

- A. Split-Faced Concrete Masonry Units
  - 1. Description: Normal weight, integrally pigmented hollow units with burnished faces as scheduled or required and with a net area of compressive strength of greater than or equal to 1900 psi.
  - 2. Facing Texture Style: Splitface
  - 3. Compliance: ASTM C 90

# **Marquette Square Dumpster Enclosure Construction**

- 4. Recycled Content: Up to 35 percent supplementary Cementitious Materials
- 5. Coloring: Integral, though-body coloring; synthetic or natural iron oxide pigments.
- 6. Integral Polymer Emulsion Water Repellent as specified by manufacturer.
- 7. Size and Shape: Standard 8"x 8" x 16"
- 8. Color: "Charcoal" Color may change as directed by Engineer.

# 2.3 GROUT

- A. Conventional Grout:
  - 1. Shall conform to ASTM C 476 and the recommendations of NCMA TEK 9-4A.
  - 2. Grout shall be proportioned to provide slump of 8 to 11 inches as measured by ASTM C 143 / ASTM C 143M.
- B. Self-consolidating Grout: Shall conform to ASTM C 476 and MSJC.

# 2.6 MORTAR

- A. Mortar for Concrete Brick Units:
  - 1. Masonry Cement conforming to ASTM C 91, Type N
  - 2. Cement Lime.
    - i. Portland Cement: ASTM C 150
    - ii. Hydrated Lime: ASTM C 207, Type S
    - iii. Portland and Lime shall be mixed to meet ASTM C 270 property specification Type N.
  - 3. Mortar Color: as directed by Engineer.
  - 4. Joint Striking: Concave
- B. Aggregate for Mortar: ASTM C 144
  - 1. Water-Repellant Admixture: Liquid water-repellent mortar admixture or manufacturer approved equal.
- C. Water: Clean and potable.

# 2.7 CLEANERS

- A. Cleaners: Non muriatic acid cleaner
- B. Cleaners: As applicable and after a test area is prepared.
  - 1. Acceptable Product: SureKlean Custom Masonry Cleaner as manufactured by PROSOCO.
  - 2. Acceptable Product: SureKlean Light Duty Concrete Cleaner (LDCC) as manufactured by PROSOCO.
  - 3. Acceptable Product: NMD-80 as manufactured by EaCo Chem Inc.
  - 4. Engineer Approved Equal

6/6/2019 04 22 00-3 Concrete Unit Masonry

#### PART 3 – EXECUTION

# 3.1 EXAMINATION AND PREPARATION

# A. Examination:

- 1. Verify field conditions are acceptable and ready to receive masonry.
- 2. Verify the foundations or bearing elements are within tolerances conforming to the requirements of ACI 117.
- 3. Verify built-in items are in proper location, and ready to receive masonry work.
- 4. Verify Concrete Brick Masonry Units are according to project specification and meet appropriate ASTM specification requirements.
- B. Preparation: Prepare surfaces and materials in accordance with MSJC Specifications for Masonry Structures.
- C. Do not proceed with installation until substrates have been properly prepared and deviations from manufacturer's recommended tolerances are corrected.

# 3.2 INSTALLATION

# A. Concrete Brick Masonry Units

- 1. Install concrete masonry units in accordance with MSJC Specifications for Masonry Structures and manufacturer's instructions.
- 2. Bond Pattern for Exposed Masonry: Running Bond.
- 3. Lay units by selecting product from more than one pallet at a time during installation.
- 4. Lay units with full mortar head and bed joints.
- 5. All cutting shall be done with masonry saw to provide, clean, sharp, unchipped edges.
- 6. Do not use masonry units with broken corners and edges in excess of ASTM C 90 and ASTM C 1634.
- 7. Temporary Formwork and Shores: Construct formwork to support reinforced masonry elements during construction.
- 8. Provide temporary bracing during installation of masonry work. Maintain in place until building structure provides permanent bracing.
- B. Control Joints: Designed to reduce restraint and permit longitudinal movement. Per NCMA Tek Note 10-2C and 10-4, proper control joint spacing is required for concrete masonry walls.

# C. Mortar and Mortar Joints:

- 1. Mortar Mixing:
  - i. Add mortar ingredients in accordance with ASTM C 270.
  - ii. Add mortar coloring
  - iii. Add water repellent admixture specified by manufacturer.
  - iv. Mix mortar components between 3 to five minutes.

6/6/2019 04 22 00-4 Concrete Unit Masonry

# **Marquette Square Dumpster Enclosure Construction**

# 2. Mortar Joints

- i. Tool exposed joints when mortar is thumbprint hard, using jointer larger than joint thickness.
- ii. Remove excess mortar smears as work progresses.
- D. Ambient Conditions: When ambient air temperature is outside the range of 40 to 90 degrees F (4.4 to 32.2 degrees C), implement procedures and comply with recommendations in accordance with MSJC Specification for Masonry Structures.
- E. During Construction and until the top bond beam course is grouted solid, keep walls covered to prevent rain or snow intrusion into the Concrete Brick cores or wall cavities.

# F. Cleaning:

- 1. After mortar is thoroughly set and cured, clean Concrete Brick Units explicitly following manufacturer's recommended cleaning instructions.
- 2. All caulking and sealant materials shall be in place and cured prior to cleaning.
- 3. Application of cleaner above 50 psi. is prohibited.
- 4. Pressure rinse with 800 to 1000 psi at a water flow rate of 6-8 gallons per minute and a 40 degree fan spray tip. Reduce water pressure to avoid damage to delicate masonry.

# 3.3 POINTING AND CLEANING

- A. Contractor shall keep masonry units, walls and surrounding work clean during construction following standard masonry practices. Mortar soiling (included but not limited to droppings, splatters, smears) shall be removed at the end of each day. Remove mortar soiling from masonry work and connecting work before its final set. Mortar droppings that adhere to the exposed face of the units shall be removed using brick/block scrap after being allowed to harden, without causing damage to the exposed face of installed brick. Remaining mortar shall be removed with a stiff fiber brush.
- B. At installation completion of Exposed Concrete Brick Masonry, tuck-point holes and imperfections in joints of all exposed masonry surfaces, completely filling with mortar.
- C. Tool to match surrounding mortar joints. After pointing hardens, and within fourteen days of finished work, clean masonry surfaces of all excess mortar soiling and dirt.
- D. All Concrete Brick Masonry shall be cleaned in strict accordance with specified manufacturer's instructions. Mild masonry detergents/cleaners and power washing systems shall be properly used. Strong acids, acid washes, or chemicals with a strong acid reaction shall not be used.

6/6/2019 04 22 00-5 Concrete Unit Masonry

# 3.4 PROTECTION

# A. Protection:

- 1. Protect installed work from damage due to subsequent construction activity on the site.
- 2. Protect masonry materials during storage and construction to prevent moisture intrusion and soilage.
- 3. During erection, cover tops of walls to prevent moisture penetration into cores of Concrete Brick and cavities of wall system.
- 4. Provide final protection and maintain jobsite conditions that ensure Concrete Brick Masonry is without damage, deterioration, or soiling.

**END OF SECTION** 

6/6/2019 04 22 00-6 Concrete Unit Masonry

# **SECTION 08 15 00.01**

# VINYL FENCING DOORS

# PART 1 – GENERAL

# 1.1 SUMMARY

- A. Section Includes
  - 1. Construction of vinyl fencing gates and doors.

# 1.2 REFERENCES

- A. Comply with the following guidelines:
  - 1. CertainTeed Bufftech Vinyl Fence Installation Guidelines
- B. Comply with applicable federal, state, and local regulations.

# 1.3 SUBMITTALS

- A. Product data:
  - 1. Submit complete materials list of items proposed for the work.
- B. Submit samples:
  - 1. Color and finish.

# PART 2 - PRODUCTS

# 2.1 MATERIALS:

- A. Vinyl Fence shall be CertainTeed Chesterfield with CertaGrain Texture Vinyl Fence or an Engineer approved equal. The color is to be determined by owner.
- B. Composition:
  - 1. Polyvinyl Chloride Compound (PVC): 80-85% by weight
  - 2. Chloroethene: Trace

# PART 3 INSTALLATION

# 3.1 PREPARATION

- A. Care of the product
  - 1. Place vinyl fence components on a non-abrasive surface, such as a drop cloth, to avoid scratching.
  - 2. Protect components during transportation to installation site to avoid damage.
  - 3. Avoid excessive force when assembling components.
  - 4. Avoid overtightening screws.

6/6/2019 08 15 00.01-1 Vinyl Fencing Doors

# **Marquette Square Dumpster Enclosure Construction**

#### B. Gates

- 1. Gate(s) must be assembled prior to fence to accurately establish space between hinge and latch posts and height of fence.
- 2. Gate requires 2" clearance under bottom rail on level ground.
- 3. When building gates in the field, ensure that 1/4-inch drain holes are drilled in bottom rail.

# 3.2 INSTALLATION

# A. Gates

- 1. Gate(s) must be assembled prior to fence to accurately establish space between hinge and latch posts and height of fence.
- 2. Gate requires 2" clearance under bottom rail on level ground.
- 3. When building gates in the field, ensure that 1/4-inch drain holes are drilled in bottom rail.

# 3.3 CLEANING

- A. Clean vinyl fence with mild detergent and a plastic scouring pad. For more stubborn stains, use a cleanser such as Soft Scrub or cleaning solution listed on warranty.
- B. Concrete is easily washed off when wet, but can also be removed when dry.

END OF SECTION


6/6/2019 08 15 00.01-2 Vinyl Fencing Doors

# PROJECT# 19-16 MARQUETTE SQUARE DUMPSTER ENCLOSURE CONSTRUCTION

CITY OF DE PERE



ENGINEER DIVISION 925 S. SIXTH ST DE PERE, WI, 54115



SHEET NO.	DESCRIPTION			
G001	TITLE SHEET			
G002	STANDARD ABBREVIATION & SYMBOLS			
C100	DEMOLITION AND UTILITY PLAN			
C101	MARQUETTE SQUARE DUMSPTER ENCLOSURE PLAN SHEET			
CITY OF DE PERE				
<b>BOARD OF PUBLIC WORKS</b>				
6/14 DATE 6/17 DATE	CITY ENGINEER  CITY ADMINISTRATOR  CITY ADMINISTRATOR  MAYOR  MAYOR			
STAMPS:				
	ERIC P. RAKERS E-30929 GREEN BAY, WI SONAL BY GIALIS			
PAGE G001				

#### LIST OF STANDARD ABBREVIATIONS MAPPING & TOPOGRAPHY SYMBOLOGY MAPPING & TOPOGRAPHY SYMBOLOGY DESCRIPTION **SYMBOL** DESCRIPTION **SYMBOL** ADT AVERAGE DAILY TRAFFIC AGGREGATE AGGR **EXISTING** PROPOSED **PLAN BENCHMARK** NORTHBOUND NC NE NO NORMAL CROWN NORTHEAST ASPH ASPHALT (SIZE AND MATERIAL) BUSH В/В BACK TO BACK EXISTING SANITARY SEWER LINE RARR BARRICADE NUMBER $\blacksquare$ NOT TO SCALE 100'-8" PVC SAN BACK OF CURB CATCH BASIN BC BK NORTHWEST PROPOSED SANITARY SEWER LINE сту CABLE TV BOX (SIZE AND MATERIAL) OIL AND CHIP BLDG O&C BUILDING Δ EXISTING STORM SEWER LINE CONTROL POINT OBLI1 OBLITERATE BENCHMARK OUTSIDE DIAMETER BACK OF SIDEWALK BOW 100'-8" PVC STM E POINT OF CURVATURE POINT OF COMPOUND CURVE FLECTRICAL BOX BSMT **BASEMENT** PROPOSED STORM SEWER LINE ST PCC PCC EROSION CONTROL - INELT PORTLAND CEMENT CONCRETE C&G CURB AND GUTTER (SIZE AND MATERIAL) PED **PEDESTAL** EXISTING WATER MAIN LINE C/C CABC CENTER TO CENTER PERMANENT LIMITED EASEMENT **(III)** FIELD INLET CRUSHED AGGREGATE BASE COURSE 100'-8" PVC WM (TEE-BEND) CB CE PVM **PAVEMENT** CATCH BASIN PROPOSED WATER MAIN LINE PRIVATE ENTRANCE GAS VALVE GV CONSTRUCTION ENTRANCE POINT OF INTERSECTION CAST IRON PIPE PRE-FORMED JOINT FILLER HEDGE EXISTING ELECTRICAL LINE CL CMP CENTERI INF PROPERTY LINE CORRUGATED METAL PIPE X POINT OF CURVE POINT ON TANGENT HYDRANT POC CNTY COUNTY EXISTING GAS MAIN LINE CLEANOUT POT POLYETHYLENE IRON PIPE 0 CONC CONCRETE POINT OF REVERSE CURVATURE CONSTR CONSTR JT CONSTRUCTION CONSTRUCTION JOINT EXISTING TELEPHONE LINE PROJ **PROJECT** LIGHTPOLE $\dot{\phi}$ PROP PROPOSED CONTROL POINT POUND PER SQUARE INCH MAILBOX COUNTY TRUNK HIGHWAY PSI EXISTING CABLE TV LINE MB POINT OF TANGENCY CTRL CONTROL JOINT PVC POLYVINYL CHLORIDE MANHOLE ELECTRIC **(E)** CTV CABLE TV EXISTING SANITARY LATERAL CY CUBIC YARD RANGE OR RADIUS REINFORCED CONCRETE PIPE MANHOLE SANITARY RCP SS SS REBAR REINFORCEMENT BAR DIAMETER EXISTING WATER SERVICE MANHOLE STORM (ST) (ST) DUCTILE IRON PIPE REM REMAINING DISCH DISCHARGE MONTORING WELL RIGHT OF WAY REQUIRED ROW RFOD ΜW DW DRIVEWAY REFERENCE LINE EAST (SEE ELEC BELOW) POWER POLE ROW RIGHT OF WAY 0 PROPERTY LINE REFERENCE POINT **EASTBOUND** SIGN BASE RR RAILROAD EBS EXCAVATION BELOW SUBGRADE \* ECS EXTERNAL CHIMNEY SEAL EASEMENT — Esm — RETAINING WALL **ELEVATION** SOUTH ELEC ELECTRIC (E WHEN USED IN LINE STYLE) SIGNAL HEAD, TRAFFIC SIGNAL **←**○ **SALVAGE** SILT FENCE EROSION CONTROL **EMB** EMBANKMENT STANDARD PEDESTAL BASE SANITARY **ENTRANCE** SOUTHBOUND EDGE OF PAVEMENT 615 EXISTING FIBER OPTIC SDWK SIDEWALK SIGNAL HEAD, TRAFFIC SIGNAL FW **FNDWALL SOUTHEAST** POLE, TRANSFORMER BASE EXC **EXCAVATION** SQUARE FEET — — — 612 · — — — EXISTING MAJOR CONTOUR **EXIST EXISTING** $\Sigma$ SHLDR SHOULDER STUMP SQUARE YARD ----- 615 -----FACE TO FACE EXISTING MINOR CONTOUR **(e)** TELEPHONE MANHOLE SS STORM SEWER FOUNDATION STOPPING SIGHT DISTANCE FIFI D FNTRANCE TEL <sup>-</sup> 612 <sup>--</sup> TELEPHONE PEDESTAL PROPOSED MAJOR CONTOUR STA STATION FERT FFRTII IZFR STANDARD STD ~~~ ~~~ ~~~~ **@** FINISHED GRADE STH STATE HIGHWAY TRUNK TREE PROPOSED MINOR CONTOUR **FLOWLINE** STM FO FOW FIRER OPTIC SEWAGE TREATMENT PLANT FRONT OF SIDEWALK STRUC1 STRUCTURE OR STRUCTURAL **PROFILE** FOOT WATER SERVICE VALVE SOUTHWES1 **FOOTING** TAN **TANGENT** 08 0GV GW BUTTERFLY WATER VALVE TOWN (T WHEN USED FOR TELEPHONE LINE) (SIZE AND MATERIAL) GAS VALVE GUY WIRE TEL EXISTING SANITARY SEWER LINE WATER VALVE $\otimes$ 8 **TEMP TEMPORARY** HIGH DENSITY POLYETHYLENE TLE TOC TOW TEMPORARY LIMITED EASEMENT HANDICAP RAMP TOP OF CURB 100'-8" PVC SAN @ 0.40% HSE HOUSE TOP OF WATER PROPOSED SANITARY SEWER LINE **GENERAL CONSTRUCTION NOTES:** HEIGHT TRANS TRANSITION HYDRANT HYD TYP **TYPICAL** INTERSECTION ANGLE ALL ELEVATIONS ARE REFERENCED TO NAVD 88. UG USH UNDERGROUND (SIZE AND MATERIAL) ICS INTERNAL CHIMNEY SEAL EXISTING STORM SEWER LINE US HIGHWAY INSIDE DIAMETER THE WORK UNDER THIS CONTRACT SHALL BE IN ACCORDANCE WITH VC VERTICAL CURVE IN INCH THE CITY OF DE PERE, CURRENT CONSTRUCTION SPECIFICATIONS AND **VERT** INLET THESE SPECIAL PROVISIONS AND PLANS, AND THE LATEST ADDITION VOL VPC VOLUME 100'-8" PVC STM @ 1.0% PROPOSED STORM SEWER LINE OF THE WISCONSIN DEPARTMENT OF TRANSPORTATION STANDARDS VERTICAL POINT OF CURVATURE INVERT SPECIFICATIONS FOR HIGHWAY AND STRUCTURE CONSTRUCTION VERTICAL POINT OF INTERSECTION VPI IRON PIPE OR PIN SPECIFICATIONS, LATEST EDITION, WHERE REFERENCED IN THE CITY VERTICAL POINT OF REVERSE CURVE JCT JUNCTION VERTICAL POINT OF TANGENCY (SIZE AND MATERIAL) LENGTH (OF CURVE) EXISTING WATER MAIN LINE WEST ĹC LONG CHORD OF CURVE ALL EROSION CONTROL MEASURES SHALL BE IN PLACE PRIOR TO WESTBOUND CONSTRUCTION AND SHALL CONFIRM TO THE WISCONSIN DEPARTMENT WATERMAIN LIFT STATION OR LUMP SUM OF NATURAL RESOURCES CONSTRUCTION SITE EROSION CONTROL AND PROPOSE 8" PVC WM WATER SHUTOFF VALVE WSO PROPOSED WATER MAIN LINE LEFT TECHNICAL STANDARDS. WATER TREATMENT PLANT MAINT MAINTENANCE wv WATER VALVE MATERIAL MATL EXISTING UTILITIES SHOWN ON THE PLANS ARE APPROXIMATE. THE WASTE WATER TREATMENT PLANT WWTF CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING EXACT PATCH SYMBOLS MANHOLE LOCATIONS AND ELEVATIONS OF ALL UTILITIES. WHETHER SHOWN OR ASPHALTIC CONCRETE PAVEMENT CRUSHED AGGREGATE 2000 MARKER POST NOT, FROM THE OWNERS OF THE RESPECTIVE UTILITIES. ALL UTILITIES BASE COURSE OWNERS SHALL BE NOTIFIED BY THE CONTRACTOR 72 HOURS PRIOR 4 44 3 PORTLAND CEMENT CONCRETE REVISIONS / ISSUES CITY OF DE PERE PAGE MARQUATTE SQUARE DUMSPTER ENCLOSURE CONSTRUCTION STANDARD ABBREVIATIONS SURVEYED ENGINEERING DIVISION 925 S. SIXTH ST DE PERE WI 54115 DRAWN KAD PROJECT # G002 AND SYMBOLS

OFFICE 920-339-4060 FAX 920-339-4071

DESIGNED

